


EAST ELEVATION

CHISANA

HISTORIC STRUCTURE REPORT



se greatly appreciate the contributions of the following people:

Crangell-Saint Elias National Park and Preserve staff, especially Chuo
udge, Superintendent; Bill Paleck, Chief Ranger; Ross Rice, District
anger; Brad Cella, Resource Management Specialist and Nick Powning,
aintenance Foreman, provided technical input and logistical support
or the preparation of this report. Thanks also to Chisana residents
t Ray McNutt's, the Overly's, and Ivan Thorat.

ois V. Hull, Secretary, Division of Cultural Resources, Alaska
egional Office typed the final report.

avid C. Anderson completed initial draft of Architectural Data
reatment drawings and existing conditions photography.

raig W. Davis, Regional Archeologist

avid E. Snow, Regional Historical Architect

obert L.S. Spude, Regional Historian

FIELD TEAM

avid C. Anderson, H.A.B.S. Architect

ike Lappen, H.A.B.S. Historian

even N. Peterson, H.A.B.S. Architect

ussell Sackett, H.A.B.S. Architect

INTRODUCTION	1
ADMINISTRATIVE DATA SECTION	5
I. PHYSICAL HISTORY AND ANALYSIS SECTION	11
A. HISTORICAL DATA	11
1. HISTORY	11
2. HISTORIC PHOTOGRAPHS.	16
B. ARCHITECTURAL DATA.	27
1. EXISTING CONDITIONS	27
a. Women's Jail.	27
b. U.S. Commissioner's Court	29
c. U.S. Commissioner's Residence	31
2. RECOMMENDED TREATMENTS.	34
a. Women's Jail.	34
b. U.S. Commissioner's Court	38
c. U.S. Commissioner's Residence	44
3. MATERIALS LISTS AND COST ESTIMATES.	48
a. Women's Jail	48
b. U.S. Commissioner's Court Alternative "A".	50
c. U.S. Commissioner's Court Alternative "B".	50
d. U.S. Commissioner's Residence.	50
e. Cost Estimates	50
4. TOOL LIST.	50
a. Hand Tools	50
b. Power Tools.	50
5. ALTERNATIVE TREATMENTS.	50
6. EVALUATION OF EFFECT OF THE RECOMMENDED TREATMENTS.	50
C. ARCHEOLOGICAL DATA	60
D. EXISTING CONDITION PHOTOGRAPHS	60
E. HISTORIC AMERICAN BUILDING SURVEY DRAWINGS	120
F. RECOMMENDED TREATMENT DRAWINGS	140

B.	BIBLIOGRAPHY	10
C.	FIELD NOTES	11

This report was prepared to meet the immediate needs of a developing park and to stabilize and restore significant cultural sources. Existing condition drawings prepared to Historic American Buildings Survey standards and Emergency Stabilization Treatments have been prepared for three historic structures in the historic Chisana Townsite. These three structures are identified as the U.S. Commissioner's Court, U.S. Commissioner's Residence and Men's Jail. Due to the simplicity of these structures the information presented in this report should be sufficient to meet management obligations and goals while providing a data base for initial treatment.

The U.S. Commissioner's Court, U.S. Commissioner's Residence and Men's Jail are the most significant structures within the proposed Chisana historic district. Built during Chisana's peak years, 1893-1920, the structures represent the simplest architectural found in the mining boom camps of Alaska's gold rush era. They represent the introduction of law and order into the Alaskan frontier. After the withdrawal of the U.S. Commissioner in 1930 the building became part of the Lou Anderton (later Pioneer Outfitters) guide outfitting service operation until c. 1969. The log structures have fallen into disrepair since then.

The proposed Chisana historic district includes the former Chisana Townsite structures on public domain. Several historic structures on the McNutt homestead, the eastern portion of the original townsite, and may be included, with owner consent, on the National Register of Historic Places nomination. Other structures on the public domain remain in the proposed district have conflicting ownership claims which need resolution.

Inventory and recordation of structures in Chisana occurred during the summers of 1982 and 1983 as part of the Wrangell-St. Elias National Park and Preserve, Historic Resource Study.

This report was originally prepared as an emergency stabilization report but several things came to light during its initial review. First of all, it is not the goal of this division to further complicate the process of treating historic structures, nor to create a document. With this in mind the report was modified to meet N.P.S. Guidelines for Historic Structure Reports. This report now contains all the components of a Historic Structure Report.

Though stabilization sounds appropriate when speaking of rehabilitation of a historic log structure, restoration cannot help but be performed. The structural aspects of log structures are performing the dual role of holding the building up as well as protecting it from the weather. In this vein, it is extremely difficult to separate stabilization treatments from restoration treatments; they become one in the

work. This will save significant time and funds that would normally be used in developing a separate package of Working Drawings and Specifications, as these are contained in this report.

Another departure from conventional Historic Structure Reports is the use of Historic American Building Survey drawings in place of existing condition drawings. Since both types of drawings record essentially the same information it saves time and funds to utilize the H.A.B.S. format for the H.S.R. and still have a H.A.B.S. record archived in Washington, D. C.

historic townsite of Chisana. These structures comprise three out of twenty which are still extant. Chisana sits between the north bank of Natchez Creek, and the south side of Chisana Airfield. Nabesna A-3 T.3 N., R.18 E., Secs: 1 and 2, (sec. 2) S/E, S/E, S/E. Sec. 1) S/W, SW, Copper River Meridian. The following are individual building locations:

Women's Jail: North west corner of Chisana Historic District approximately 70' north of U.S. Commissioner's Courthouse. Nabesna A-3R. 18 E. T 3 N. Sec. 2, S/E, S/E, Copper River Meridian.

U.S. Commissioner's Courthouse: Western end of Chisana approximately 30' east of U.S. Commissioner's residence. Nabesna A-3R. 18 E., T. 3 N., Sec. 2, S/E, S/E, Copper River Meridian.

U.S. Commissioner's Residence: At the western extreme of Chisana 30' west of the U.S. Commissioner's Courthouse. Nabesna A3R. 18 E., T. 3N., Sec. 2, S/E, S/E, Copper River Meridian.

These three structures fall into management category B according to N.P.S. 28 Cultural Resource Management Guidelines. This category states that management should preserve and maintain structures in categories of significance 2a and 2b, as described in "Management Policies" (Chapter 5, pp. 3-4). Structures must meet all of the following criteria to be classified category B:

- A. The structure meets National Register criteria individually or as part of a network, district, or multiple resource.
- B. The structure is not incompatible with a primary park theme.
- C. The structure has a continuing or potential use benefiting the park or a leased operation, based upon design, condition, location and use.

The historic structures in Chisana will be listed on the "Classified Structures" as of August, 1984.

Planning documents proposing treatments and use are the Park Management Plan and the General Management Plan.

Treatments proposed in this report are "Restoration" according to N.P.S. Management Policies, Section V, page 10. Treatments involve the process of recovering the general appearance of a structure by the removal of incompatible human-caused accretions and the replacement of missing appropriate. Restoration of exteriors and interiors may be complete.

This division has been developed with full concurrence of the Par
Superintendent and reflect his views on what the structures will b
used for. Further consultation with the Superintendent is expecte
during design development of use options.

1. HISTORY

According to the reminiscence of old timers and present residents of Chisana, the three log structures herein described were built during the Chisana gold rush (ca. 1913-1914) and were used as the U.S. Commissioner's Residence, U.S. Commissioner's Court and Women's Jail. Some residents associate the structure with Anthony "Tony" Dimond, first commissioner in Chisana and, later, Alaska's delegate to Congress, 1933 to 1944.¹ Research has yet to prove association--the early records of the town (1913-1940) were destroyed by fire, historic photographs are lacking for this area of the town and information from contemporary newspapers scanned thus far inconclusive.

The Chisana Strike:

During the spring of 1913 two veteran prospectors, Billy James and Nelson, crossed from the White River drainage into the headwaters of the Chisana River. At the mouth of what would become Bonanza Creek they discovered gold. Nelson returned to Dawson for supplies and out the word, which quickly spread to other Alaska-Yukon camps. That summer, idle miners and merchants turned their attention to the diggings. The Chisana stampede had begun.²

An estimated 5000 stamperders headed for the diggings from Fairbanks, Nome, the coastal towns and even Seattle that summer of 1913. Prospectors staked creeks and hills for ten miles around Bonanza Creek while two groups of merchants established townsites, one at the mouth of Bonanza Creek called Bonanza City and one down Chathenda Creek, a mile from Chisana River, called first Chathenda City, then Chisana. The establishment of a post office September 30, 1913.⁴

Town building at Chisana followed the same pattern as other Alaska rush era cities -- Circle and Eagle, Rampart and Fairbanks, Iditarod and Ruby. First, merchants staked a townsite, built stores and shops and then, among other things, called for legal protection and property rights. In late summer a U.S. Commissioner and a deputy marshal were appointed for the new mining district.

The U.S. Commissioner:

Tony Dimond, one time prospector and, more recently, a Valdez law firm was appointed by U.S. District Judge Robert Jennings as Chisana's first commissioner.⁵ His duty would be to insure proper recording of mineral claims and other land claims, the adjudication of local cases, and multitudinous trivial duties of a first rung government official.

as household hardware was not much dealt in in the early years of the territorial settlements.

The walls, door, and windows finished, the spaces between logs, and every other space visible, was chinked, stuffed, with moss, driven in tight by suitably shaped sticks."⁹

Chisana Commissioner's residence has a burm around the sill which is kept out the winter cold. The buildings also have ornamental tails, diamond shape log decorative touches, attached log shelf and pin connectors for door hinges (see physical description section). The extended porch and window details can be seen in contemporary buildings (see historic photographs).

Chisana's Decline:

The extent of the placer deposits proved limited to only Bonanza Creek and Glacier Creek and their short tributaries. The population declined from a reported 500 in 1914 to a total of 175 in the entire

Chisana River drainage in 1920.¹⁰ Business declined consequently the town's cabins were abandoned or, for most, burned for firewood. Athenda Creek eroded its bank, taking other cabins.

The Commissioner's fees proved far less than Tony Dimond had hoped for. In July 1914 he quit the position and left the district. Chisana was the beginning of his distinguished career as mayor of Valdez (10 years), Alaska's sole delegate to Congress (11 years) and U.S. District Judge (9 years). His first replacement never appeared in Chisana. The second stayed less time than Dimond.¹¹ In 1915, Ant McGettigan, who worked for Dimond as recorder, was appointed Commissioner. He was replaced in 1920 with the national change in politics and Aaron E. Nelson became Chisana's last commissioner (1920-1930).¹¹ McGettigan remained in the area as miner and postmaster until 1937.¹²

In the 1930's the population of Chisana consisted of a handful of prospectors and merchant Charles A. Simons. Chisana's role as a minute trading center passed with the 1939 transfer of the post office to Nabesna, a mining camp forty miles to the west.¹³

Hunting and Guiding:

Although hunting guides had been in the Chisana area before the rush, Chisana became a stop for parties hunting the Wrangells during the 1890s and 1920s. Following World War II and the advent of fly-in hunting,

... the Commissioner's residence and court. A
addition was attached to the west wall of the Commissioner's court.14
nderton died ca. 1962; his Pioneer Outfitters was continued in
operation by the Overly family. In ca. 1969 they moved a mile west
earer the Chisana River, in a more isolated setting, acquiring a
homestead at that local. In 1980 the historic townsite of Chisana
except for the portion included in Ray McNutt's homestead) became a
part of Wrangell-St. Elias National park and Preserve.

Chisana, July 1982, June 1983, Terry Overly, Chisana, June 1983.
Ray McNutt, Chisana, July 1982, June 1983.

-) Terrane M. Cole, "Historic Use of the Chisana and Nabesna Rivers in
Alaska", State Alaska, Department of Natural Resources, May 1983.
Stephen R. Capps, The Chisana - White River District USGS Bulletin
630 (Washington, D. C.:GPO, 1916) pp. 25-27.
-) Cole, "Historic Use of the Chisana," pp. 10-13.
-) Melvin B. Ricks, Alaska's Postmasters and Postoffices 1867-1900
(Ketchikan, Alaska: Tongass Publishing Co., 1965), pp. 11-12.
-) Nome Daily News, November 4, 1913; Cordova Daily Alaskan, September
18, 1913.
-) Ernest Gruening, The State of Alaska (New York: Random House, 1954)
pp.342-343; Morgan Sherwood, Big Game in Alaska, A History of
Wildlife and People (New Haven, Connecticut: Yale University
Press, 1981), pp. 45-46.
-) Ibid.; Cordova Daily Alaskan, October 6, 1913.
-) See footnote 1; Melody Webb Grauman field notes, September 8-10,
1978, copies in National Park Service files, Anchorage, Alaska.
-) William Ogilvie, Early Days on the Yukon (London: J. Lane, 1906)
pp. 299-301.
- 0) Alden M. Rollins, compiler, Census of Alaska: Number and
Inhabitants, 1792-1970 (Anchorage: University of Alaska, 1971)
pp. 1920-4.
- 1) Mary Childers Mangusso, "Tony Dimond," Alaska Journal Autumn 1978,
pp. 11-23.
- 2) Ricks, op.cit.,p.12.
- 3) Cole, "Historic Use of the Chisana," pp. 18-20.
- 4) Ray McNutt, Chisana, June 1983; Elizabeth Hickathier, June 1983.

First Avenue looking east, Chisana (Shushanna) early 1914. All buildings in original townsite were log construction. Miner's Home Bar and Shushanna Cafe burned ca. 1960s. Courtesy L. Zacharias Collection, Alaska Historical Library.

"Gambling house, Shushanna, Alaska". ca. 1914. Note peg work detail and roof detail. Courtesy L. Zacharias Collection, Alaska Historical Library.

"City Jail, Shushanna, Alaska" Probably men's jail ca. 1914, between women's jail and commissioner's court. No longer stands. Courtesy L. Zacharias Collection, Alaska Historical Library.


Zacharias residence, Chisana ca. 1914. Note roof details and peg work. Courtesy L. Zacharias Collection, Alaska Historical Library.

MINERS HOME

BAR



First Avenue looking east, Chisana (Shushanna) early 1914. All buildings in original townsite were log construction. Miner's Home Bar and Shushanna Cafe burned ca 1960s. Courtesy L. Zacharias Collection,





QD-10

QD-10

City Jail Shushanna Alaska.

"City Jail, Shushanna, Alaska" Probably men's jail ca. 1914, between women's jail and commissioner's court. No longer stands
Zacharias Collection
Court





Zacharias residence, Chisana ca. 1914. Note roof detail.
Courtesy L. Zacharias Collection, Alaska Historical Library

1. Existing Conditions

This section will include a verbal and graphic description of the surfaces and foundations of all three buildings. Investigations were through visual observations with no physical alteration or removal of layers.

The buildings being described will include: 1) The Women's Jail, the U.S. Commissioner's Court, and 3) the U.S. Commissioner's residence. These buildings represent the three main structures remaining in the northwest quadrant of the Old Chisana Town site.

At this time no stabilization or other emergency measures have been taken to insure the preservation of these buildings. For further documentation of these structures refer to the included photographs.

a. Women's Jail

A one story, one room, saddle-notched log cabin with porches at the east and west ends, with the entry on the east end. The porch on the east end has a small storage room made from 1 inch wide plank width planks.

1) Roof

Originally it was a sod roof on 3-4 inch wide log ceiling planks. A board and batten roof was placed over the sod one time but has deteriorated almost completely. Exposed roof members have deteriorated and show considerable decay. From under the ceiling members appear to be in good condition. One section of the south side has collapsed due to rotted wood and snow loads. Condition and extent of decay on each of the roofing members need to be determined at the time of treatment. All ceiling planks over the porch are very decayed.

The super structure of the roof ridge beam and plate logs appear to be in good condition with little deterioration. Butting poles on the eaves are rotted and missing in places.

2) Walls, Doors and Windows

All of the log walls above grade are in poor structural shape. Some of the chinking is missing causing several cracks and holes in all sides. Two holes high up on the west wall are apparently a vent (filled at present with a wad of cloth) either caused by a missing section of log. Logs are unpeeled, 8 inches in diameter and hewn flat on the inside.

The porch storage room walls heavily weathered. No treatment visible. Support posts are loose and showing signs of weathering.

e frame). The shelving system around the south window is in excellent condition.

e window on the west end appears to have been a later addition. It is a different style from the north and south windows and is essentially large enough to crawl out of (not very efficient in a fire). The frame is loose, all boards are weathered and the stops are missing as is the glazing. The shelf above the window is in good shape.

e entry door on the east end of the cabin is loose on its hinges. The hinges (stamped metal) are rusted. The surface mounted lock set is broken and what appears to have been a dead bolt is missing. A patterned fabric covers the lower part of the inside of the door and is deteriorating. A window in the upper part of the door has one broken pane. The glass looks as though it has been replaced often and the same work of the window appears to have been hastily adapted to different sizes of glass over the years. Weather stripping, in the form of rolled bead cotton wicks, is missing or deteriorated around the door joints.

e door to the storage room will not shut due to settling of the porch planks. Hinges are badly racked and loose. The wood pivot latch is in working order.

3) Floors and Foundation

The floor in the main cabin consists of 1 inch random width planks nailed to 2-3 inch diameter log stringers. The stringers are placed on grade at 2 feet to 2 feet 6 inches on center. The floor shows a slight bow and is heaving slightly in the middle. There are no holes or hollow spots in the boards, but, they appear loose in places. Condition of the stringers is unknown though they are probably rotting since they are on grade and exposed to the ground moisture.

e porch floor is heavily weathered and deteriorating in places. The boards are loose and the two stringers underneath are rotting considerably.

e sill logs on all sides of the building are in the final stages of decay. Soft and yielding to the touch, they show signs of dry rot and there may be carpenter ant activity. The sill logs are set directly on the ground with no evidence of any sub-foundation or rock piling. There may have been a garden along the south side at one time but everything has decomposed - including part of the foundation along the wall.

with a low-sloped shed roof on the addition on the west side of building. Originally a one room cabin, the porch extension on both end enclosed what had been a 7 foot 6 inch cantilevered over the entry. The addition on the west side was constructed in 1960's and consists of 5-6 inch logs notched into the 8-12 foot log main cabin.

1) Roof

There are two roofs on the structure. Original roof was a sod roof with sod placed on top of a split-baling. The ceiling members appear to be in very good condition underneath and there is very little evidence of leakage. The top of the ceiling members may be considerably deteriorated due to the constant contact with the sod roofing. Some of the sod has begun to rot down between the ceiling members and onto the floor. The butting poles at the ends of the ceiling members appear to be in good condition, indicating that the ceiling members have not had problems occurred by wicking.

The newer roof is heavily weathered. (There does not appear to be any vegetation growing on the roof). This roof consists of a double layer of roofing felt (horizontal layer over vertical layer) over 1 inch wide random width boards supported by 2 x 4 inch rafters. The rafters are nailed above the sod layer by means of a 3 x 4 inch purlin or purlins placed directly above the place logs along both eaves. There is a slight sway along the eave of the newer roof. The secondary purlins have been extended 2 1/2 feet beyond the original roof in front and not beyond in the back, thus keeping the end walls from deteriorating. The purlins show signs of rapid deterioration.

The porch roof was added after the second roof was built but the main roof extends over it. The porch roof consists of 1/2" inch plywood over 3 inch rafter logs at 16 inches on center. The plywood is deteriorating, sagging and water stained. The slope of the addition roof is less than 2 inches in 12 inches and leakage is considerable at the junction of the addition roof and the second roof on the main cabin. It leaks badly and there is no evidence of any flashing. Resolution of the detailing at that junction and at the junction of the addition roof where they go beyond the butting pole of the old roof was not fully worked out and involved a great deal of moss chinking - most of which is missing.

Structurally, the main roof of the cabin is sound, although the purlins, rafters and ridge beam all show serious weathering, from wicking at the ends. Eave logs at all three end walls of the main cabin which are decayed and/or broken. All of the original peg holes which supported the butting poles are gone or unusable.

are all bound above grade. The south wall seems to lean to the right 3-4 inches from the eave log up to the ridge. Most of the chinking is intact, but not all. Exposed ends of the logs are weathered and wicking has caused decaying of the ends - especially on those logs which have sawn ends. The ends of the eave logs are usable. There are vents in both end walls with mosquito netting over the north wall.

Most of the logs on the west wall have been notched 2 inches deep to accept the 5-6 inch logs of the addition on that side. The window was removed and the lower logs cut to make a doorway into the addition. No indications of a door or the door frame that was set there. The window that was removed was apparently the one which was then used in the west wall of the addition. Door jambs made from rough sawn 1 inch boards and trimmed only on the inside. All trim work and window and door jambs painted green. (Probably a recent paint job because the paint is not faded.)

The window on the east side is intact with the glass missing. The frame was built around a manufactured sash. The sash is held in place with wood stops. Logs on outside hewn flat on both sides of the window to allow trim to lay flat. Trim made from 1 inch x 4 inch rough sawn boards.

The entry door is made with diagonal planking on the outside face of vertical boards. It has a wood handle inside and out with a wood pivot bolt each inside. The hinges are still tight. The jamb is made from 1 1/2 inch x 6 1/2 inch boards with 1 1/2 inch x 5 inch trim on one side of the outside and 1 inch x 5 1/2 inch trim on all sides of the inside. Inside logs are hewn flat to take thick trim boards.

3) Walls, Doors (Porch)

The porch walls consists of 5 1/2 inch-6 inch logs horizontally stacked with Hudson Bay corners. Corner splines are loose on most joints. Horizontal logs are notched around the splines and nailed to splines in very few places. Large cracks are opening up between logs toward the tops of the corner posts - due to settling of the outside corners (or potentially, to heaving under the door toward the center of the wall). The posts on each side of the door are similar in detail to the corner posts. The door posts are also notched to the eave log which doubles as the header log over the door.

The joint between the main cabin log extensions and the porch wall logs consists of a spline nailed to the ends of the main cabin logs and wedges in the porch wall logs (very similar to the Hudson Bay cornering). Splines are loose here also, but the joint is fairly tight. The chinking along this joint is also missing as it is through the porch walls.

corners and up to 16 inches at the top. The logs are in good condition due to the fact that they are less than 30 years old and are well maintained. Wicking has not yet begun to deteriorate them even though the roof does not cover any of the ends. Many of the logs have saw kerf running through them across the grain (as much as 80% of the width through the logs). Mildew is forming on some of the top logs because of the leakage through the roof.

The window is intact and the glass unbroken on the west wall. The trim is placed outside and inside of the full rounded width of the log. The sash seems to have been placed on its side in the frame, since the sashes and stiles would otherwise match up to those on the window on the east side of the main cabin.

5) Floors and Foundations

The floor in the main cabin (and the porch addition) consists of 1 inch random width boards nailed to stringers and on grade. The floors in the main cabin and the addition are sagging and loose. In the addition they are rotten and in the porch many are missing altogether. The stringers in most cases also seem rotten and in the porch many of them are missing.

The sill logs are 12-14 inches in diameter for the main cabin and the east and west logs extend all the way out to the end of the porch to support the corner posts. All the sill logs are rotted and deteriorating. There is no apparent footing (either rocks or other material) under any of the sill logs. The sill logs on the addition are also showing signs of decay and there is evidence of carpenter ants in some places.

c. U.S. Commissioner's Residence

A one story, two room, saddle-notched building with the porch walled in with Hudson Bay corners). The building is south with the entry through the porch on the south side. A higher level of detail in this building than in the other buildings of this report with fabric covering walls and split-log trim on all openings as well as three decorative elements. A gravel and soil berm circles the building with an open area in front of the front entry.

1) Roof

General condition of the roof is poor to bad. The roof consists of two systems, the newer roof placed on top of the original. The original system consists of split 4-7 inch logs (split down) laid across the ridgebeam, purlins and plate logs. The newer system (probably 6-10 inches deep) covered the logs and was held

gone and the ends of the ceiling logs are decayed and rotting. Some of the ends have fallen off. The butting poles are missing in places and deteriorated elsewhere. The underside of the ceiling logs are covered with green burlap and there are several bad water stains indicating leakage through the roof. The ridge beam is sound as are the purlins. The plate logs are considerably deteriorated. The rotted plate logs coupled with leaning walls make the roof sway along both eaves. A collar log spans between the purlins in the rear and the purlins extend 16" beyond the end of the ceiling logs.

The newer roof, a 2 inch x 4 inch rafter system sheathed with 1 inch x 8 inch boards and covered with rolled asphalt roofing, is supported by 3 x 4 inch purlins laid on top of the sod roof above the plate logs. Rafters and purlins are deteriorated. Much of the asphalt roofing is missing or badly torn and there are willows growing through the roof from the sod beneath. Fascia boards (1 x 10 inch) are warped, weathered and/or missing. This newer roof extends 2 feet beyond the gable end of the original roof in front and 10 inches beyond in the rear. Boards are extended to the ends of the plate logs and ridge beam and the fascia of the new roof (probably to hold the roof down in winds).

2) Walls, Windows, and Doors (Main Cabin)

All main cabin walls are built from 7-11 inch diameter unpeeled logs, hewn flat inside. Most logs appear to be sound with the exception of the plate logs on both sides and the bottom three log courses on the exterior walls. These lower logs have been covered with berming from the outside and are rapidly deteriorating. The side walls lean in about 4 inches at the top due to the decayed plate logs and the lack of support along the window jambs. Eave logs are in good shape - they do not extend beyond the side walls. The north and south walls of the main cabin are in good condition with the exception of some missing chinking on the north wall.

The same green burlap fabric that covers the ceiling also covers the walls. The fabric is brittle in many places. It is water stained around and below leaks and faded where the sun or the heat of the stove strikes it. In places the fabric is held in place with brass upholstery tacks and in others by staples. The water stained areas are decayed and deteriorate at a touch.

Shelving systems around both side windows and above the rear (north) window are in good condition, except where thrown out of line by the upheaval of the floor boards.

Window frame, sill, and sash in north wall in good condition. Window frames and sashes are weathered but intact on east and west walls. The glass is cracked or missing in both panels of the west window and all three panels of the east window. All of the building compound is dried

3) Walls, Windows, and Door (Porch Enclosure)

The walls to the porch consist of Hudson cornered infills above a 2 to 6 foot saddle-notched knee wall. Log the east and west walls are separated by 1/2 inch to 1 inch from the ends of the main cabin logs. Both front corners of the porch have dropped approximately 4 inches from the center of the wall (probably because of the deterioration of the sill logs). Except for the three log courses and the plate logs, all of the logs themselves are in good condition. Gaps have opened up below the cave log on the west wall with much of the chinking deteriorating and eroded.

Front door is in excellent condition with the exception of the covering on the outside which is torn and deteriorating. The trim around the windows and door frame is interconnected with a single trim piece. The settling of the corners of the porch has caused the trim around the windows to become separated and the pegs holding the trim in place to loosen. The settling has also racked both window frames and broken the glass in the frames. The window frames are heavily weathered.

Fabric on the inside walls of the porch is a white canvas or oil cloth. All of the fabric is water stained and mildewed and in advanced stages of decay. In many places the canvas is serving to hold moisture and debris, thus accelerating the rate of decay of the logs, especially at the bottom, as well as the canvas itself. The shelving systems in the porch are thrown together and built up of old crates and scraps of wood. Many are broken and falling apart.

4) Floors and Foundations

The floor in the main cabin consists of 4 inch x 8 inch average, random width, rough sawn planks on log stringers on grade at 2 feet to 6 feet on center. There is considerable heave in the center of the floor where it appears to be 2 to 3 feet higher than at the east and west walls. In many places the boards are raised completely clear of the stringers. Substantial gaps have opened up between the boards in many places.

The porch floor is the same construction as the main cabin floor and is in poor to bad condition with a patch having already been attached on the east side of the floor. The boards are very soft along the west wall. Presently old catalogs and newspapers are piled along the west end, rotting and deteriorating the boards as the acid leaches out.

The condition of the log foundation throughout is poor to bad. Sill and spandrel logs rest on grade with no foundation or

below the original outside grade. The seaming of the logs of each wall caused rapid deterioration of the bottom three logs of each wall including the sill logs. The sill logs have become "one with the soil."

2. RECOMMENDED TREATMENT

Many of the preparations and treatments are the same for all of the buildings. The treatments vary only in detail on each building. Since the buildings are of similar construction, it is the individual detailing on each that sets it apart from the others. (For individual variations and details see the drawings at the back).

This report is written to provide technical support for an experienced craftsman. Most of the work that has been done and needs to be done on these buildings is straight forward and requires common sense as much as proven carpentry skills. The craftsman should familiarize himself with the existing conditions and detailing before beginning any work on the buildings.

The sill logs and spandrels need to be replaced with pressure treated timbers on all of the buildings. This entails jacking the building off of the rotted logs. Once the bad logs have been removed the soil must be removed from under each wall. The 10" x 10" pressure treated timbers are then set on undisturbed soil. At this point it will be necessary to rip two of the wall logs in half so that they will rest flat on the new sill timbers. The first course of logs (including the half logs) is then attached to the sill members with drifted rebar.

A major problem for all of the buildings has been moisture in the soil around the sill logs. A 4 inch to 6 inch bed of gravel should then be placed in the floor joist space. Drain tile is also set on gravel and sloped (1/8 inch in 12 inch minimum slope) toward the rear of the building. Most of the drainage problem will occur below the eaves of the roof therefore the tiles should be centered below the eave line. A layer of gravel over the tile is then set before replacing the soil to the original grade.

Roof preparation for each building will require the removal of everything above the ceiling planks. Once the ceiling planks are exposed they can be checked for evidence of decay. At this point each building will have a slightly different procedure.

a. WOMEN'S JAIL, TREATMENT

1) Roof:

a) Remove all sod and covering materials from ceiling planks.

the old logs and drawings) and set in place.

e) Remove all ceiling planks that show excessive deterioration including planks that are less than 1 1/2 inch to 2 inches thick after removing surface decay and those planks that have badly rotted or broken ends.

f) Replace all planks that were removed.

Note: Replacement should be the same basic size and shape - toolmarks should be applied to the underside and the ends with broad axes (adzes.)

g) New butting poles should be pre-drilled (1 1/2 inch holes) for the 1 1/2 inch square pegs that hold them in place at the eave logs.

h) Butting poles should be spiked to the ends of the ceiling planks to prevent sagging.

i) Rafters (2 1/4 inch x 6 inch) are placed 16' on center on top of the ceiling planks starting flush with the outer edge of the ceiling planks on the west end of the roof.

j) Blocking (2 inch x 6 inch) should be provided between the rafters above the side walls (as per drawings).

k) Roof sheathing (1 inch x 8 inch) is applied with 12d nails across the rafters.

l) Roofing felt (30 pound) should be rolled out over the sheathing starting from the bottom of each eave. (Applied with 1 inch roofing nails - 4 inch lap top and bottom.)

m) Galvanized, rolled tin, 24 gauge in 30 inch sheets is to be cut into 30 inch x 30 inch sheets and treated with kerosene to remove the oils.

n) The tin sheets are then applied across the bottom of the eave with a 6 inch lap on the sides and 6 inch laps between each row. (Asphalt roofing tar is to be applied between each sheet where they lap.) The sheets are nailed with 1 1/4 inch leadhead roofing nails - tar applied over each exposed nailhead.

o) Paint roof brown when tar sets up.

holes between logs.

c) A piece of log should be cut to fit into the west wall.

d) Remove all boards and posts of the stor

e) At this point the floor boards on the po

will be replaced.

f) Replace all the posts with 4 inch x 4 inch posts, attaching posts to the logs with log spikes. Toenail existing posts to the plate log, ceiling plank, and floor boards with 12d nails.

g) Apply new boards (1 inch x 8 inch) to the floor in same configuration as original boards.

h) Rehand existing storage room door and rework the door mechanism.

3. Floors:

a) Existing floorboards and stringers should be removed.

b) Excavate to the bottom of the sill timber

c) Attach 2 inch x 6 inch rim joists to the north and south sill timbers, 1 inch below top of sill.

d) Toenail 2 inch x 6 inch joists 16 inches apart center flush with top of rim joists.

e) Floor boards (1 inch x 8 inch) nailed to joists with 12d nails - stagger the butt joints at least 2 joists apart adjacent board.

f) Excavate porch area to 12 inches below the sill timber.

g) Fill with 4 inches of gravel.

h) Set 6 inches x 6 inches treated timbers in gravel and fill back against the front timber.

i) Nail 1 1/2 inch x 10 inches floor boards to timbers.

b) Build new frame for opening with 1/2 inch
8 inch rabbet on inside edge (see detail).

c) Flatten rounded logs on outside wall around
window opening. Flatten logs approximately 5 inches back from opening
make the wall a consistent 6 1/2 inches thick at the opening.

d) Shim window square and level and nail with
d nails. Chink around edges with moss.

e) Rip 4 inch logs in half for trim pieces and
attach trim with 16d nails. (See detail for mitre cuts.)

f) Cut glass to fit frame. Set in a bed of
caulking and attach 1/2 inch by 3/4 inch stops (milled on site) with 6
finish nails.

g) Chisel rabbet along edge of south window
where kerf is 1/2 inch deep.

h) Remove broken glass from south window and
replace.

i) Set new glass in bead of caulking and attach
with stops with 6d finish nails.

j) Replace glass in front door.

k) Replace hinges on front door.

l) Remove old lockset.

m) Install new lockset and deadbolt.

b. U.S. Commissioner's Court:

The court building has two alternative treatments.
Alternative "A" involves removing the addition that was put on in the
1950's. Alternative "B" involves the treatments necessary to
rehabilitate the building in its present configuration.

b.a. Alternative "A":

1) Addition:

a) Remove all roofing and ceiling members from
the addition on the west side.

b) Remove window frame and sash intact (can
be taken with this as it will be reused in the cabin)

d) Remove all floor boards and stringers.

e) Repair any damage to the surrounding environment which was caused by the addition (re-sod area and fill trenches).

2) Roof: (Should be worked on after west wall is done.

a) Remove all sod and covering materials from ceiling planks.

b) Scrape and brush all signs of rot and decay from the surface of all ceiling planks.

c) Existing eave logs should be removed (by jacking up the plate logs on both sides).

d) New eave logs should be notched (patterned after the old logs and drawings) and set in place.

e) Remove all ceiling planks that show excessive deterioration, including planks that are less than 1 1/2" to 2" thick after removing surface decay and those planks that have badly rotted or broken ends.

f) Replace all planks that were removed (Note: Replacement should be the same basic size and shape - toolmark should be applied to the underside and the ends.)

g) New butting poles should be set in notches in eave logs and spiked in place (butt the poles over the eave log at the south wall of the main cabin).

h) Butting poles should be spiked to the ends of the ceiling planks to prevent sagging.

i) Rafters (2 inches x 6 inches) are placed 16 inches on center with 3 foot outriggers extending out to create an overhang 2 inches to 3 inches past the ends of the longest purlins or plate logs at both ends.

j) Blocking (2 inches x 6 inches) is placed between the rafters, above the plate logs on the east and west sides.

k) Roof sheathing should run diagonally across outriggers and rafters after insulation is placed between the rafters.

l) Roofing felt (30 pound) should be rolled across the sheathing starting from the bottom of each eave (1/2 inch

n) The tin sheets are then applied across bottom of the eave with a 6 inch lap on the sides and 6 inch between each row. (Asphalt roofing tar is to be applied between sheet where they lap.) The sheets are nailed with 1 1/4 inch lead roofing nails and tar applied over each exposed nailhead.

o) Paint roof brown when tar sets up.

3) Walls (Main Cabin):

a) Remove and replace all logs on the west wall at a time. (Existing logs have notches from the addition wall leave an opening for the window which was removed from the west wall the addition. Logs on both sides of the windows should be drilled pinned together with #4 rebar. Pinning should occur 4 inch on each side (staggered from one log to the next) from the window opening

b) Loose chinking should be removed.

c) New moss chinking should be jammed into cracks and holes between logs.

4) Walls (Porch):

a) Remove board chinking from both sides of south wall.

b) Remove top log of east and west walls (below the plate logs).

c) Remove top log of south wall (2 pieces below the eave log).

d) Remove nails that attach slotted horizontal logs to splines.

e) Renail splines to all posts and ends of main cabin logs. (Lift individual logs and place 20d nail between each log and other log.)

f) Replace top logs under eave log and porch logs and renail ends of slotted logs to splines.

g) Remove loose chinking from all logs.

h) New moss chinking should be jammed into cracks and holes between logs.

removed.

b) Excavate to the bottom of the sill tim

c) Excavate a 4 inch to 6 inch deep
north to south down center of foundation.

d) Set 4 inch x 6 inch treated timber
undisturbed soil (bottom flush with bottom of sill timbers.

e) Attach 2 inch x 6 inch rim joists
and west sill timbers, flush with top of sills.

f) Toenail 2 inch x 6 inch joints
center flush with rim joists.

g) Floor boards (1 inch x 8 inch) na
joists with 12d nails - stagger the butt joints at least 2 jo
each adjacent board.

6) Windows and Doors:

a) Install window frame and sash in west

b) Set glass in east and west window
glazing points and seal with glazing compound.

c) Replace hinges and install clasp o
door.

bb. Alternative "B"

1) Addition on West Side:

a) Jack up addition walls and remove a
below grade.

b) Excavate 10 inches to 12 inches belo
under the walls and fill trenches with 4"-6" of gravel.

c) Set 6 inches x 6 inches treated tim
the gravel. (Top should be flush with top of sill timbers
cabin.)

d) Rip bottom logs of north and south w
half so that they rest flat on the sill timbers.

e) Attach bottom logs to sill timbers
rebar (10 inch lengths).

gs.)

2) Roof:

- a) Remove all sod and covering materials from planks.
- b) Scrape and brush all signs of rot and decay from the surface of all ceiling planks.
- c) Existing eave logs should be removed (by pulling up the plate logs on both sides).
- d) New eave logs should be notched (patterned after the old logs and drawings) and set in place.
- e) Remove all ceiling planks that show signs of deterioration including planks that are less than 1 1/2 to 2 inches thick after removing surface decay and those planks with badly rotted or broken ends.
- f) Replace all planks that were removed. Replacement should be the same basic size and shape - tool should be applied to the underside and the ends.
- g) New butting poles should be set in notches between the eave logs and spiked in place (butt the poles over the eave log at the outer wall of the main cabin).
- h) Butting poles should be spiked to the ends of the ceiling planks to prevent sagging.
- i) Rafters (2 inches x 6 inches) are placed on center with 3 foot outriggers extending out to create an overhang of 12 inches to 3 inches past the ends of the longest purlins or logs at both ends.
- j) Rebuild the tops of the north and south walls of the addition with those logs that can be reused. Replace any that are too badly damaged. The logs should be scribed to fit between the butting pole and the ceiling planks of the main cabin.
- k) Plane the top of the wall flat from the top of the addition's west wall plate log to the top end of the rafters on the main cabin.
- l) Put 2 inches x 6 inches blocking between the rafters between the walls of the addition.

triggers and rafters of the main cabin
between the rafters.

n) Rafters (2 inches x 6 inches) are placed
inches on center at the addition and the bottom of the rafter should
flush with the ends of the sheathing and nailed to the sheathing of the
main cabin.

o) Rafters should be placed over the north and
south walls.

p) Blocking (2 inches x 6 inches) should
be placed above the plate log of the addition.

q) Roof sheathing (1 inch x 8 inches) should
be placed across the rafters of the addition after insulation
is installed.

r) Roofing felt (30 pound) should be rolled
across the sheathing starting from the bottom of the addition and to
bottoms of the two eaves (double layer with 18 inch overlaps on the
addition - single layer with 4 inch overlaps on the main cabin).

s) Galvanized, rolled tin, 24 Gauge in 30 inch
x 48 inch sheets are to be treated with vinegar to remove the oil
before applying.

t) The tin sheets are then applied across the
bottom of the eave with a 6 inch lap on the sides and 6 inch lap
between each row (8 inch laps all around on the roof of the addition).
Asphalt roofing tar is to be applied between each sheet where they lap.
The sheets are nailed with 1 1/4 inch leadhead roofing nails with tar
applied over each exposed nailhead.

u) Galvanized 30 inch, 24 Gauge flashing
is applied to the valley at the junction of the main cabin over the
roofing sheets on the addition and under the sheets of the main cabin.

v) Paint roof brown when tar sets up.

w) Ceiling boards (1 inch x 6 inch) are applied
to the underside of the rafters running north south. If necessary,
a first board should be set above the north and south walls for
nailer.

3) Walls (Main Cabin):

a) Loose chinking should be removed.

b) New moss chinking should be jammed into a
cracks and holes between logs.

- b) Remove top log of east and west walls (below the plate logs).
- c) Remove top log of south wall (2 pieces below the eave log).
- d) Remove nails that attach slotted horizontal logs to splines.
- e) Renail splines to all posts and ends of cabin logs. (Lift individual logs and place 20d nail between each log.)
- f) Replace top logs under eave log and place logs and renail ends of slotted logs to splines.
- g) New moss chinking should be jammed into cracks and holes between logs.

5) Floors (Main cabin and porch):

- a) Existing floorboards and stringers should be removed.
- b) Excavate to the bottom of the sill timbers.
- c) Excavate a 4 inch by 6 inch deep trench north to south down center of foundation.
- d) Set 4 inch x 6 inch treated timber on foundation (bottom flush with bottom of sill timbers).
- e) Attach 2 inch x 6 inch rim joists to north and west sill timbers, flush with top of sills.

rim joists.

g) Floor boards (1"x8") nailed to joists with 16 nails - stagger the butt joints at least 2 joists on each adjacent board.

6) Floor (Addition):

a) Remove existing floorboards and stringers.

b) Excavate to the bottom of the sill timbers in the main cabin and fill with gravel up to the bottoms of the addition sill timbers.

c) Set 2"x6" floor joists on grade (toenail the sill timbers) at 24" on center.

d) Floorboards (1"x6") nailed to joists with 16 nails - stagger butt joints at least 2 joists on each adjacent board.

7) Windows and Doors:

a) Square up and shim from and sash of west window.

b) Set glass in east and west windows with glazing points and seal with glazing compound.

c) Replace hinges and install hasp on port door.

c. Commissioner's Residence, Treatment:

1) Roof:

a) Remove all sod and covering materials from ceiling planks and green fabric from ceiling and ridge/purlins.

b) Scrape and brush all signs of rot and decay from the surface of all ceiling planks.

c) Remove all ceiling planks that show extensive deterioration including planks that are less than 1 1/2" thick after removing surface decay and those planks that have bad rot or broken ends.

d) Remove plate logs on east and west wall (This will entail providing a temporary support for the remaining ceiling planks and also plumbing up both walls. Once the plates are removed the walls must be shored out at the top.)

f) Replace all planks that were removed. Every plank should have a 6 inch dovetail extending beyond the end of the planks. (Note: Replacements should be the same basic size shape - tool marks should be applied to the underside of each plank.)

g) New butting poles should be ripped in half to fit over the dovetails at the ends of the planks.

h) Rafters (2 inch x 6 inch) are placed 16 inch on center on top of the ceiling planks starting flush with the 4 inch diameter log fascia at each end of the ceiling planks.

i) Fascia boards (1 inch x 6 inch) should be nailed to the ends of the rafters with 12d nails.

j) Attach the butting poles, sliding them onto the dovetails from above and nailing them to the ends of the ceiling planks with 20d nails.

k) Roof sheathing (1 inch x 8 inch) is applied with 2d nails across the rafters.

l) Roofing felt (30 pound) should be rolled out over the sheathing starting from the bottom of each eave. (Applied with 1 inch roofing nails to 4 inch lap top and bottom.)

m) Galvanized, rolled tin, 24 gauge in 30 inch rolls is to be cut into 30 inch x 30 inch sheets and treated with kerosene to remove the oils.

n) The tin sheets are then applied across the width of the eave with a 6 inch lap on the sides and 6 inch laps between each row. (Asphalt roofing tar is to be applied between each sheet where they lap.) The sheets are nailed with 1 1/4 inch flat head roofing nails with tar applied over each exposed nailhead.

o) Paint roof brown when tar sets up.

2) Walls (Main cabin):

a) Remove all cloth covering walls.

b) Carefully remove trim from east and west walls. (Trim will be reused.)

c) Carefully remove window frames and sashes from east and west windows. (Frames and sashes will be reinstalled.)

e) Cut a 2 inch x 2 inch board 2 1/2
taller than the window opening and set it into the trench. Nail
place with 20d nails.

f) Replace window frames, sashes, and
Nail the frame to the opening on all sides to secure the wall logs.

g) Remove all loose chinking.

h) New moss chinking should be jammed
cracks and holes between logs.

3) Walls (Porch):

a) Remove loose chinking and fabric from
walls.

b) Remove nails that attach horizontal
splines.

c) With both the sill timbers and the
logs replaced the corner post should be tight. Toenail it at
and bottom with 16d nails.

d) Renail splines to posts and main corner
ends.

e) Check top logs (under eave and platform)
to see that they are the right size. If too large, trim down
for a tighter fit. If too small remove and replace with a larger log.

f) Renail logs to splines.

g) New moss chinking should be jammed
cracks and holes between the logs.

4) Floors:

a) Remove existing floor boards and stringers.

b) Excavate level with the bottom of the
timbers.

c) Dig a trench 4 inches to 6
north-south in the center of the floor.

top of the sill timbers in the porch and 1 inch below the sill in main cabin.

f) Floor boards (1 inch x 8 inch) are nailed to joists with 12d nails - stagger the butt joints at least 2 joist each adjacent board.

5) Windows and Doors (Main cabin):

a) Set new glass in east and west windows glazing points and seal with glazing compound.

b) Replace missing trim piece on west window.

c) Replace the hinges on the door to the main cabin.

d) Reshim window frames on north wall behind door. Tighten trim pieces.

e) Replace glass in both windows of north wall and set in a bead of caulk. Attach 1/2 inch x 3/4 inch stops with 6d finish nails.

6) Windows and Doors (Porch):

a) Reshim window frames.

b) Reset trim around windows.

c) Replace glass and set in bead of caulk. Attach 1/2 inch x 3/4 inch stops.

3. MATERIAL LIST AND COST ESTIMATES

a. Women's Jail

1) Lumber, Rough Sawn, White Spruce

1"x8" x 8'	76	406 bf.
1"x6" x 8'	20	80 bf.
Subtotal		485 bf.
2"x6" x 8'	42	336 bf.
2"x6" x 10'	18	180 bf.
Subtotal		516 bf.
4"x4" x 8'	4	44 bf.
4"x12" x 8'	40	1280 bf.
Total		2325 bf.

10"x10" x 8'	8	534 bf.
6" x6" x 6'	4	<u>72</u> bf.

Total	606 bf.
-------	---------

- 3) Galvanized, Rolled Tin, 24GA
30" roll (to be cut into 30"x30" sheets)

200'

- 4) Rolled Roofing Felt, 30#, Black

300 sq. ft. Required	3 rolls
----------------------	---------

- 5) Reinforcing Steel (Rebar)

#4 (16" lengths)	30'
------------------	-----

- 6) Nails:

Galv. 16d Common	25#
Galv. 12d Common	25#
Galv. Roofing Nails 1"	20#
6d Finish	1#
Log spikes, 6"-7"	30#

- 7) Galv. Leadhead roofing nails
1 1/4" 50#

- 8) Hardware:

4" strip hinges	2 pr.
Face mount, lockset	1
Face mount, deadbolt	1

- 9) Glass: Single strength

12" x 10 1/2"	1
11 3/8" x 19 1/2"	1
25 1/8" x 20 3/8"	1

- 10) Silicone Caulking, Clear 1 tube

- 11) Asphalt roofing tar 2 gal.

- 12) Brown paint (oil base, gloss) 2 gal.

14) Logs:

8" Dia. (Min.) x 16'	2
4" Dia. (Min.) x 22'	2

15) Lumber, rough sawn, white spruce

1 1/2" x 10" x 6'	16	120 bf.
-------------------	----	---------

16) Douglas Fir, #1, Clear

2" x 8" x 8'	2	21 bf.
--------------	---	--------

b. U.S. Commissioner's Court (Alt. "A")

1) Lumber, Rough sawn, White Spruce

1"x8" x 8'	200	1067 bf.
2"x6" x 8'	60	480 bf.
2"x6" x 10'	36	<u>360</u> bf.
	Subtotal	<u>840</u> bf.
3"x8" x 10'	30	600 bf.
	Total	2507 bf.

2) Timber, Douglas Fir, pressure treated with
omated Copper Arsenate, Select Structural (No-1) full dimension
gh cut, labeled (LP-22 Ground Contact 40).

10"x10" x 8'	12	800 bf.
4"x6" x 8'	3	<u>48</u> bf.
	Total	848 bf.

3) Galvanized, rolled tin, 24GA
30" roll (to be cut into 30"x30" sheets)

900

4) Rolled roofing felt, 30# black

900 Required	9 rolls
--------------	---------

5) Reinforcing Steel (Rebar)

#4 (16" lengths)	50'
------------------	-----

	Galv.	16d Common	50#
	Galv.	12d Common	50#
	Galv.	Roofing nails	50#
	Log Spikes	5"x6"	50#
7)	Galv.	Leadhead roofing nails	
		1 1/4"	100#
8)	Hardware:		
		4" strap hinges	2 pr.
		Hasp & Staple, 4"	1
9)	Glass, single strength		
		28" x 34 1/4"	2
10)	Silicone Caulking, clear		
			1 tube
11)	Asphalt roofing tar		
			2 gal.
12)	Brown paint (oil base, gloss)		
			3 gal.
13)	Insulation, R-13		
		15 1/2" Batts	10 rolls
14)	Drain Tiles:	6" perforated PVC pipe	
		8' lengths	10
		90° elbows	2
15)	Logs, unpeeled, White Spruce		
		8" Dia. (min.) x 20'	3
		3" Dia. (Min.) x 20'	2
		3" Dia. (Min.) x 12'	2
		8" Dia. (Min.) x 20'	9
			(only on Alt. "A")

(to be added to those items on Att. "A" list)

1) Lumber, Rough sawn White Spruce

1"x8" x 8'	30	160 bf.
1"x6" x 8'	80	320 bf.
Subtotal		480 bf.
2"x6" x 12'	16	192 bf.
Total		672 bf.

2) Timbers: Douglas Fir, pressure treated with
Chromated Copper Arsenate, Select Structural (No-1), full
dimension, rough cut labeled (LP-22 Ground Contact).

6"x6" x 8'	5	120 bf.
2"x6" x 10'	10	100 bf.
Total		220 bf.

3) Galvanized rolled tin, 24 GA

30" roll	400
----------	-----

4) Roll roofing felt, 30# black

330 Ruired	4 rolls
------------	---------

5) Reinforcing Steel (Rebar)

#4 (16" lengths)	10'
------------------	-----

12) Brown paint (oil base, gloss)

1 gal.

13) Insulation, R. 19

15 1/2" Batts	3 rolls
---------------	---------

14) Drain Tile; 6" perforated PVC Pipe

8' lengths	4
90° elbows	1

d. U.S. Commissioner's Residence

1) Lumber, Rough Sawn, White Spruce

2) Timber, Douglas Fir, Pressure treated with (Chromated Copper Arsenate, Select Structural (No-1), full dimension rough cut labeled (LP_22 Ground Contact).

10"x10" x 8'	22	1467 bf.
6"x6" x 8'	26	624 bf.
4"x6" x 8'	1	16 bf.
3"x6" x 8'	2	24 bf.
Total		2131 bf.

30" roll (cut into 30"x30" sheets)

800'

3) Rolled roofing felt, 30#, black

500# Required 6 rolls

4) Reinforcing steel (Rebar)

#4 (16" lengths) 80'

5) Nails:

Galv. 20d Common	50#
Galv. 16d Common	50#
Galv. 12d Common	50#
Galv. Roofing Nails, 1"	50#
Log Spikes, 10"	30#
Log Spikes, 6"	50#

6) Galv. Leadhead roofing nails

1 1/4" 100#

7) Hardware

4" Strap hinges	1 pr.
4" Hasp & staple	1

8) Glass: single strength

14"x20"	2
16"x20"	2
12"x9 3/4"	2
20 1/2"x14 1/2"	1

9) Silicone caulking, clear 1 tube

12) Insulation, R-19

15 1/2" Batt 9 rolls

13) Drain tile: 6" perforated P.V.C. Pipe

8' lengths 13

90° elbows 2

14) Logs: Unpeeled, White Spruce

9" Dia. (Min.) x 26' 3

7" Dia. (Min.) x 30' 2

6" Dia. (Min.) x 30' 3

15) Timber, Rough sawn, White Spruce

3"x8" x 10' 40 800 bf.

3"x6" x 10' 50 750 bf.

Total 1550 bf.

e. Cost Estimates

1) Hand Tools \$12,000

2) Women's Jail

a) Materials 2,600

b) Labor 8,690

c) Transport Materials 9,298

d) TOTAL \$14,454

3) Commissioner's Residence

a) Materials \$ 6,004

b) Labor 8,008

c) Per diem 500

d) Transport Materials 15,340

e) TOTAL \$29,852

b) Labor	9,280
c) Per diem	600
d) Transport Materials	<u>13,680</u>
e) TOTAL	\$33,122
5) Return of Materials	<u>3,950</u>
6) GRAND TOTAL	\$93,378

This estimate was prepared by Maintenance Foreman Nick Powning and good through the summer of 1984.

1)	Bow Saw, 36"	1
2)	Handsaw, Crosscut	2
3)	Bow saw blades, 36"	3
4)	Hatchets	2
5)	Axe	1
6)	5-Ton hydraulic jacks	8
7)	8' Step ladders	2
8)	Shovels	3
9)	"Comealong" winch	2
10)	Framing hammers, 20 oz.	3
11)	Hammer, 16 oz.	1
12)	Sledge hammer, 8 lb.	2
13)	Log chain, 3/4" links	30'
14)	Log tongs	2
15)	Crow bar, 36"	2
16)	Steel pry bar, 5'	1
17)	Flat "wonder" bar	1
18)	Tape measure, 25'	2
19)	Tape measure, 50'	1
20)	Builder's level (Transit)	1
21)	Tripod (for transit)	1
22)	"Cats Paw"	2
23)	4' level	1
24)	2' level	1
25)	Utility matt knife w/retracting blades)	2
26)	Extra Matt knife blades (5/packet)	3 pkts.
27)	Chalkline/plumb bob	2
28)	Wood chisels (1/2", 3/4", 1", 1/4", 1/2", 2")	1 set
29)	Pliers	2
30)	Builder's square	2
31)	Putty knives, 1", 3"	2 ea.
32)	Caulking gun	1
33)	Tin snips	3
34)	Adze	1
35)	Draw knives	2
36)	Wheel barrow	1
37)	Screw drivers; #2 phillips	2
38)	Screw drivers; #2 slotted	2
39)	Coarsle rasp	1
40)	Pencils	10
41)	Triangular metal file	2
42)	Paint brushes 4"	4
43)	8" finish plane	1
44)	Carborundum stone	1
45)	Broad Axe	1

b. Power Tools

1) Portable generator	1
2) Extension cords, 100'	2
3) Power worm drive saw, 7 1/2"	1
4) Circular saw blades, 7 1/2"	
cross cut	5
rip	2
5) Electric drill, 1/2"	
var. sp., Rev.	1
6) Drill Bits:	
speed bore bits 3/8"=1 1/2"	1 set
speed twist bits 1/16"-1/2"	1 set
1/2" wood twist bit, 2' long	2
7) Chain saw	1
8) Chains for chain saw, 24"	
cross cut chain	1
rip chain	1
9) Oil for chain saws	1 gal.
10) Pre-mix fuel for chain saw	10 gal.
11) Spark plugs for chain saw	2

5. Alternative Treatments

These alternatives take into consideration the fact funds may not be available for the recommended treatment.

a. No Further Treatment: This alternative would in further water damage and deterioration of Chisana Cabins from Wrangell-Saint Elias' severe weather conditions. Routine maintenance would continue. (This alternative is not recommended.)

b. Exterior Preservation Treatments Only: This alternative would include all essential work recommended for the exterior of the building; all roof work, replacement of deteriorated walls, sills and repair of windows and door. Routine maintenance would continue. (This alternative is not recommended because the only interior work left would be the floor and it would have to be removed to replace sill logs.)

c. Interior Adaptive Use Treatment Only: This alternative would include only floor plank replacement and would not fully stabilize deterioration of historic fabric. (This alternative is not recommended.)

Of all the alternative treatments, "b" is the preferred treatment because if these items were accomplished the structure would be effectively stabilized from deterioration.

a. Discussion

The following determination of effect of the recommended treatments is made in accordance with section 800.4(b) of Advisory Council on Historic Preservation regulations, "Protection of Historic and Cultural Properties". The council's criteria reads as follows:

A federal, federally assisted, or federally licensed undertaking shall be considered to have an effect on a National Register property eligible for inclusion in the National Register (districts, sites, buildings, structures, and objects, including their settings) when any condition of the undertaking causes or may cause any change, beneficial or adverse, in the quality of the historical, architectural, archeological, or cultural character that qualifies the property under the National Register Criteria.

The cabins are currently being nominated to the National Register of Historic Places. The architectural and historical qualities included in this National Register Nomination are briefly outlined in the following statements to be used in applying the criteria of effect.

Wooden details on the Commissioner's buildings and the Women's Club show outstanding log craftsmanship, from hand carved wooden door frames and hinges to decorative diamond shaped, wood details around the trim.

These structures are among the best remaining of early log buildings of Gold Rush Alaska.

b. Evaluation of Effect

1) No Effect: Recommended treatments having no adverse effect on the qualities of Chisana Cabins that qualify them for National nomination to the National Register are as follows:

a) There are no recommended treatments with no effect.

2) No Adverse Effect: Recommended treatments that are considered as having an overall beneficial effect on the Chisana Cabins are as follows:

a) All replacement of rotted roof, floor and structural timbers with new material insuring that as much historic fabric as possible is retained even if higher labor cost is incurred.

b) Removal of encroaching vegetation and sediments.

3) Adverse Effect: Recommended treatments that are considered as having an adverse effect on the qualities of U.S. Commissioner's Court, U.S. Commissioner's Residence, and Women's Jail that qualify them for individual nomination to the National Register of Historic Places are as follows:


a) No Adverse Effect is anticipated from treatments recommended in this report.

sources. A survey will be scheduled and executed prior to any ground disturbing activities being conducted. All required reports and compliance documentation will also be completed.

Existing Condition Photographs, Dave Anderson, June 1983


Photograph 1
Women's Jail, Chisana
Northeast Oblique.

Photograph 2
Women's Jail, Chisana
East Elevation.



Photograph 3
Women's Jail, Chisana
South Elevation.


Photograph 4
Women's Jail, Chisana
West Elevation.



Photograph 5
Women's Jail, Chisana
North Elevation.




Photograph 6
Women's Jail, Chisana
"Hole-in-Roof" Detail, South Side.




Photograph 7
Women's Jail, Chisana
Collapsed Ceiling, South Side.


Photograph 8
Women's Jail, Chisana
Interior; West wall, shelf & window.



Photograph 9
Women's Jail, Chisana
Exterior; Window on north wall.




Photograph 10
Women's Jail, Chisana
Interior; Window on north wall.




Photograph 11
Women's Jail, Chisana
Interior; Shelf detail, south wall.


Photograph 12
Women's Jail, Chisana
Northwest corner, log connections.



Photograph 13
Women's Jail, Chisana
Floor planks, porch.





Photograph 14
Women's Jail, Chisana
Corner bracing at sill logs.





Photograph 15
U.S. Commissioner's Court
South Elevation.

Photograph 16
U.S. Commissioner's Court, Chisana
West Elevation.



Photograph 17
U.S. Commissioner's Court, Chisana
North Elevation.


Photograph 18
U.S. Commissioner's Court, Chisana
East Elevation.



Photograph 19
U.S. Commissioner's Court, Chisana
Junction of the ceiling timbers,
butting pole, eave log and
plate log w/newer roof above
ceiling members




Photograph 20
U.S. Commissioner's Court, Chisana
V-notched log corner; showing
junction of addition logs and
newer roof.



Photograph 21
U.S. Commissioner's Court, Chisana
Ceiling & North wall, showing split-
log ceiling members and peeled
purlines & ridge beam.



Photograph 22
U.S. Commissioner's Court, Chisana
Window in East wall - logs hewn to
receive flat trim pieces.



Photograph 23

U.S. Commissioner's Court, Chisana
Front entry to main cabin with hewn
logs at trim; trim missing on
right side.



Photograph 24

U.S. Commissioner's Court, Chisana


Junction of main cabin logs and
porch logs (spline just visible
between second and third porch logs
on right)



Photograph 26
U.S. Commissioner's Court, Chisana
Detail of Hudson Bay corner and
splines from interior of porch.




Photograph 27
U.S. Commissioner's Court, Chisana
Southwest corner of addition




Photograph 28
U.S. Commissioner's Court, Chisana
Junction of sill log and Hudson
Bay corner post.

Photograph 29
U.S. Commissioner's Residence, Chisana
Southwest oblique





Photograph 30
U.S. Commissioner's Residence, Chisana
South Elevation.

Photograph 31
U.S. Commissioner's Residence, Chisana
West Elevation.




Photograph 32
U.S. Commissioner's Residence, Chisana
North Elevation.

Photograph 33
U.S. Commissioner's Residence, Chisana
East Elevation




Photograph 34
U.S. Commissioner's Residence, Chisana
Roof detail with vegetation and
present occupant.

Photograph 35
U.S. Commissioner's Residence, Chisana
Eave detail with newer roof over decaying
ceiling members (note sag in roof line).



Photograph 36

U.S. Commissioner's Residence, Chisana
Collar log connecting extended purlins
(note 8" overhang of rewer roof).



Photograph 37

U.S. Commissioner's Residence, Chisana
Newer roof extension over entry on south
side supported by purlins and ridge board.




Photograph 38
U.S. Commissioner's Residence, Chisana
Canvas covering ceiling, looped around
purlins and ridge beam.




Photograph 39

U.S. Commissioner's Residence, Chisana

Interior of entry to main cabin - note
water stained burlap and seperating wind
trim.




Photograph 40
U.S. Commissioner's residence, Chisana
Junction of main cabin logs (right)
and porch logs.



Photograph 41

U.S. Commissioner's Residence, Chisana


Hudson Bay post at southeast corner of porch




Photograph 42


U.S. Commissioner's Residence, Chisana

Front window with racked frame and
seperating trim (note pegs nolding trim
in place).



CHISANA





PLAN



U.S. COMMISSIONER'S COURT
 U.S. COMMISSIONER'S RESIDENCE
 CABIN
 SHOP
 PRISON CABIN
 PRISON CABIN
 NO CORRAL

1. SECOND N.P. NELSON CABIN
 M. RAY MOUNTT - UNFINISHED CLASH
 N. RAY MOUNTT - STORAGE SHED
 O. RAY MOUNTT - OLD CLOAK
 P. RAY MOUNTT - COOKHOUSE
 Q. RAY MOUNTT - STORAGE SHED
 R. RAY MOUNTT - GARAGE
 S. RAY MOUNTT - MAIL CABIN
 T. RAY MOUNTT - RESIDENCE
 U. SHOPS-HOUSE
 V. MEAT CLOAK

23'-0" x 8'-0"

10'-0" x 3'-0"

14'-0"

3'-9"


12'-10"


23'-0"

8'-6"

3'-0"


U.S. COMMISSIONER'S COURT
 SCALE 3/8" = 1'-0"
 TRUE NORTH






NORTH ELEVATION

SCALE = 3/8" = 1'-0"



EAST ELEVATION



WEST ELEVATION

MATERIAL NOTES:

ORIGINAL BUILDING:

- WALLS- 9" TO 11" LOGS, UNPEELED WITH "V" NOTCH AT THE CORNERS. INTERIOR SURFACES HEWN TO FACILITATE DRYING WHEN CONSTRUCTED. INTERIOR DOOR AND WINDOW TRIM PAINTED DARK EMERALD GREEN. NO INDICATION OF INTERIOR WALL COVERING.
- FLOOR- 1 1/4" X RANDOM WIDTH (7 1/2" TO 12") ROUGH SAWN SPRUCE PLANKING NAILED TO LOG STRINGERS AT 3' 0" ON CENTER. STRINGERS LOCATED ON GRADE. NO INDICATION OF ADDITIONAL FLOOR COVERING.
- ROOF- AS INDICATED ON DRAWINGS.

FRONT ADDITION:

- WALLS- 5 1/2" LOGS, UNPEELED WITH HUDSON BAY CORNERS CHINKED WITH MOSS. 14" TENCH SURFACE HEWN. NO COVERINGS.
- FLOOR- SAME AS MAIN CABIN. SOME REMOVED WITH DRY EXPOSED.
- ROOF- SAME AS MAIN CABIN.

WEST ADDITION:

- WALLS- 5" PEELED LOGS, SADDLE NOTCHED CORNERS, CHINKED WITH MOSS. NO INTERIOR COVERINGS.
- FLOOR- 1" X RANDOM WIDTH (6" AVERAGE) ROUGH SAWN PLANKING ON LOG STRINGERS AT 3' 0" ON CENTER. THE STRINGERS REST ON GRADE. NO OTHER FLOOR COVERINGS ARE EVIDENT.
- ROOF- 5" LOG RAFTERS AT 1' 4" ON CENTER, COVERED WITH RANDOM WIDTH, ROUGH SAWN SPRUCE PLANKING COVERED WITH TWO LAYERS OF ROLLED ROOFING. SOD ADDED ON TOP FOR INSULATION PURPOSES.

NOTE: THE 5" LOG ADDITION WAS CONSTRUCTED IN THE 1960'S. THE SECOND ROOF OVER THE MAIN CABIN WAS ALSO ADDED AT THAT TIME.


BLACK, 2 PLY ROLLED ROOFING --
OVER RANDOM WIDTH PLANKING

5" LOG RAFTERS AT 1' 4" O/C


5" AVERAGE LOG DIAMETER
PINNED WITH STEEL SPIKES




SECTION
SCALE




SECTION B-B







WEST ELEVATION



NORTH ELEVATION



EAST ELEVATION



SOUTH ELEVATION

MATERIAL NOTES

WALLS - 7" TO 9" UNPEELED LOGS, INTERIOR FACE MEANT TO FACILITATE DRYING WHEN CONSTRUCTED LOGS ARE COVERED WITH 1/2" STICK POLES. PARTS FROM GLAZED WOODEN FUEL BOXES, AND MOSS. SURFACE IS COVERED WITH DARK GREEN BURLAP WHICH IS STRETCHED AND TACKED TO SURFACE. LOGS JOINED WITH A SADDLE NOTCH.

FLOOR - 1" X RANDOM WIDTH (17" AVERAGE) ROUGH SAW PLANKING WHICH IS NAILLED TO WOODEN STUDS AT 2'-0" ON CENTER. THAT REST ON GRADE. NO EVIDENCE OF ANY FLOOR COVERING.


CEILING - SAW SPRUCE PLANK ZELING, RESTS ON 9" AVERAGE LOG PURLINS. THE CEILING AND PURLINS ARE COVERED WITH DARK GREEN BURLAP. MOSS AND SOOT ON TOP OF CEILING PROVIDED 5" OF INSULATION. IN LATER YEARS NEW LOGS WERE ADDED TO A 1' X 6" RIFLED, 1' X 6" ROUGH SAW PLANKING AND A ONE PIECE ROLLED ROOF COVERING WERE ADDED.

FRONT ENTRY - 7" TO 9" UNPEELED LOGS FOR BOTTOM THREE LOGS. NOTCH AT A LATER PERIOD THE WALLS WERE TOTALLY ENCLOSED WITH 1" LOGS AND LOGS ON CORNERS. CONSTRUCTION INDICATES THAT THE FRONT ENTRY ORIGINALLY OPENED UP INTO A PORCH.


INTERIOR SURFACE HAS BEEN HEAVY FLAT TO FACILITATE DRYING AND COVERED WITH A HEAVY WEIGHT WHITE CANVAS COVERING.

FLOOR - 1" X RANDOM WIDTH (17" AVERAGE) ROUGH SAW PLANKING. A SECOND SURFACE OF SIMILAR PLANKING HAS BEEN ADDED ON THE EAST 1/2 OF THE ENTRY FLOOR. NO EVIDENCE OF ANY FLOOR COVERING.

CEILING - CONSTRUCTION AT IN WEST GABLE. INTERIOR SURFACE COVERED WITH WHITE CANVAS.



SECTION A - A
SCALE 3/8" = 1'-0"




SECTION C - C

UNPEELED LOG SLAB TRIM

7/8" X 1/2" STOP

3/4" X 2 3/4" SPRUCE SILL


DOWEL



POLE AND LOG SLAB SHELF

WINDOW ELEVATION

SCALE: 1 1/2" = 1'-0"




PUTTY ON OUTSIDE

SINGLE STRENGTH (ROLLED)
CLEAR GLASS

WHITE SPRUCE


WINDOW SECTION

FULL SCALE




DOOR ELEVATION

SCALE: 1 1/2" = 1'-0"




SECTION - DOORWAY

SCALE: 1 1/2" = 1'-0"



PLAN


SCALE 3/8" = 1'-0"




EAST ELEVATION



NORTH ELEVATION





- 1" x 5" ROUGH SAWN RIDGE CAP
- RANDOM WIDTH & THICKNESS LOG SLAB PLANKING
- 5" OF MOSS/SOD
- SPLIT LOG CEILING WITH 12" AVERAGE WIDTH
- 5" LOG POLES, PEGGED
- 2" LOG POLE & SLAB SHELVES PEGGED INTO WALLS
- 1" TO 12" LOG WALLS, SADDLE TIED CORNERS. ONLY THE ST ELEV HAS PEIELED LOGS
- 0 HOLES FROM REMOVED ALL FURNITURE
- RANDOM WIDTH (8") PLANK DORING
- G STRINGER, ON GRADE




SECTION B-B

F. Recommended Treatments I







⑤ EAST ELEVATION
SCALE: 1/8" = 1'-0"










⑥ NORTH ELEVATION
SCALE: 1/8" = 1'-0"




⑦ EAST SECTION A-A
SCALE: 1/8" = 1'-0"




⑧ NORTH SECTION B-B
SCALE: 1/8" = 1'-0"







① Box Plot
Date: 10.10.20




FOUNDATION & FLOOR FRAMING PLAN
DATE: 2-1-80






EAST LANS




2 SATU ELAVATION













40153-2-2529




(1) EAST ELEVATION




(2) SOUTH ELEVATION







1 FOUNDATION PLAN











2 FLOOR PLAN



2 WEST ELEVATION



2 SOUTH ELEVATION



NATIONAL REGISTER OF HISTORIC PLACES INVENTORY -- NOMINATION FORM

FOR FEDERAL PROPERTIES

RECEIVED

DATE ENTERED

SEE INSTRUCTIONS IN HOW TO COMPLETE NATIONAL REGISTER FORMS
TYPE ALL ENTRIES -- COMPLETE APPLICABLE SECTIONS

1 NAME

HISTORIC Chisana Historic District

AND/OR COMMON Shushana, Chathanda City or Johnson City

2 LOCATION

STREET & NUMBER An irregular cluster of structures extending westward approximately one fourth mile from the southeast end of the Chisana airstrip parallel to Johnson Creek.

CITY, TOWN Chisana

— NOT FOR PUBLICATION

CONGRESSIONAL DISTRICT

STATE Alaska

VICINITY OF
CODE 02

COUNTY CODE

Southeast Fairbanks Div. 24

3 CLASSIFICATION

CATEGORY	OWNERSHIP	STATUS	PRESENT USE	
<input checked="" type="checkbox"/> DISTRICT	<input type="checkbox"/> PUBLIC	<input checked="" type="checkbox"/> OCCUPIED	<input type="checkbox"/> AGRICULTURE	<input type="checkbox"/> MUSEUM
<input type="checkbox"/> BUILDING(S)	<input type="checkbox"/> PRIVATE	<input checked="" type="checkbox"/> UNOCCUPIED	<input checked="" type="checkbox"/> COMMERCIAL	<input checked="" type="checkbox"/> PARK
<input type="checkbox"/> STRUCTURE	<input checked="" type="checkbox"/> BOTH	<input checked="" type="checkbox"/> WORK IN PROGRESS	<input type="checkbox"/> EDUCATIONAL	<input checked="" type="checkbox"/> PRIVATE RESIDENCE
<input type="checkbox"/> SITE	PUBLIC ACQUISITION	ACCESSIBLE	<input type="checkbox"/> ENTERTAINMENT	<input type="checkbox"/> RELIGIOUS
<input type="checkbox"/> OBJECT	<input type="checkbox"/> IN PROCESS	<input type="checkbox"/> YES RESTRICTED	<input type="checkbox"/> GOVERNMENT	<input type="checkbox"/> SCIENTIFIC
	<input type="checkbox"/> BEING CONSIDERED	<input checked="" type="checkbox"/> YES UNRESTRICTED	<input type="checkbox"/> INDUSTRIAL	<input type="checkbox"/> TRANSPORTATION
		<input type="checkbox"/> NO	<input type="checkbox"/> MILITARY	<input type="checkbox"/> OTHER

4 AGENCY

REGIONAL HEADQUARTERS (If applicable)

Wrangell-St. Elias National Park and Preserve

STREET & NUMBER

P.O. Box 29

CITY, TOWN

Glennallen

VICINITY OF

Alaska

5 LOCATION OF LEGAL DESCRIPTION

COURTHOUSE
REGISTRY OF DEEDS, ETC.

Magistrate's Office

STREET & NUMBER

State Office Building

CITY, TOWN

Fairbanks

STATE

Alaska

6 REPRESENTATION IN EXISTING SURVEYS

TITLE

CONDITION

CHECK ONE

CHECK ONE

☐ EXCELLENT☒ DETERIORATED☒ UNALTERED☒ ORIGINAL SITE☒ GOOD☒ RUINS☒ ALTERED☐ MOVED DATE _____☒ FAIR☐ UNEXPOSED

DESCRIBE THE PRESENT AND ORIGINAL (IF KNOWN) PHYSICAL APPEARANCE

The Chisana historic district comprises 20 historically significant log structures. Most of the structures date from the winter of 1913-14, others from the post-1930 period when the airstrip was built and gold market prices jumped from \$20/ounce to \$12/ounce, and the post-1950 period and the growth of hunting guide service companies. The log structures reflect interior Alaska and Yukon Territory building practices with their extended roof beams and porches. Some log cabins have built-up eaves which keep cold air from seeping inside. The extreme temperatures of 50 degrees below or more required other heat saving techniques in chinking, chimney and stove placement, and outhouses.

The gold rush era log cabins retain their integrity, though most are being used for guide service functions or as summer residences. Changes include metal roofs (from tin can cans to aluminum and tar) instead of sod, new foundations (one of cement) instead of bare logs on tundra, and metalbestos stove pipe. Wood heat is still used. Small solar cells power batteries for lights and radios. Chisana is without electricity, telephone, sewage, or water works. The airstrip and a difficult pack horse trail are the town's link to the nearest town. Thus any introduction of non-indigenous materials is costly. All structures within the Chisana historic district are built of local timber.

BUILDINGS AND SITES CONTRIBUTING TO THE CHARACTER OF THE DISTRICT (see map):

U.S. Commissioner's Court: ca. 1913-14, log cabin, one-story, gabled roof. In fair condition; ca. 1960 small addition to west wall and wood plank roof added. Vacant.

U.S. Commissioner's Residence: ca. 1913-14, log cabin, one-story, gabled roof. In fair condition. ca. 1960s wood plank roof added. Vacant.

Women's Jail: ca. 1913-14, log cabin with a porch facing east and a gabled roof. Roof deteriorating.

Saloon: ca. 1913-14, log cabin with a small porch facing east and a gabled roof with a second (ca. 1960) roof covering it. In poor condition.

Earl Herst Cabin: ca. 1913-14, log cabin, gabled roof. In fair condition.

Historic Post Office: ca. 1913-14, log cabin, 1½ stories high with cold cellar and a gabled roof. Recently refurbished.

Cache: ca. 1913-14, log cabin, one-story high with gabled roof. Recently

First N.P. Nelson Cabin: ca. 1913-14, log structure with three connecting rooms and a gabled roof.

Sidney "Too Much" Johnson Cabin: ca. 1913-14, log structure with gabled roof, cold cellar, and storm porch. In fair condition.

Lou Anderton Barn and Corral: Date unknown, log structure. Vacant.

Second N.P. Nelson Residence: ca. 1930, log structure with gabled roof and a cold cellar. Recently refurbished.

Log Shed. Date unknown.

Old Cache: ca. 1913-14, log structure, one-story, gabled roof. In fair condition.

Mercantile, now Wrangell R ranch cookhouse: ca. 1913-14, log structure, gabled roof and porch. Concrete foundation and cellar. Refurbished.

Storage Shed. Date unknown.

Garage. Date unknown.

Mail Cabin. Date unknown.

Log Residence: Date unknown.

Billy James Residence Cabin: ca. 1913-14, log structure with a gabled roof. Good condition.

Additionally, four Native grave houses stand on ridge northwest of town. The site of the Native village is below (south) the ridge (all outside historic district).

CONTRIBUTING STRUCTURES

Cabin under construction (n.d., recent).

Smokehouse (n.d., recent).

Meat cache (n.d., recent).

SITUATION SHEET

ITEM NUMBER

7

PAGE

ver and laundry (n.d., recent)

mill (n.d., recent). Machinery from ca. 1940, rough cut, sawmill. Powered
Willy's jeep motor.

khouse (n.d., recent).

00-1499	— ARCHEOLOGY-HISTORIC	— CONSERVATION	— LAW	— LANDSCAPE ARCHITECTURE	— RELIGION
00-1599	— AGRICULTURE	— ECONOMICS	— LITERATURE	— SCIENCE	— SCULPTURE
00-1699	— ARCHITECTURE	— EDUCATION	— MILITARY	— SOCIAL/HUMAN	— THEATER
00-1799	— ART	— ENGINEERING	— MUSIC	— PHILOSOPHY	— TRANSPORTATION
00-1899	— COMMERCE	— EXPLORATION/SETTLEMENT	— POLITICS/GOVERNMENT	— OTHER (SPECIFY)	— Craftsmanship
00-	— COMMUNICATIONS	— INDUSTRY			
		— INVENTION			

CIFIC DATES 1913-1934 BUILDER/ARCHITECT Various

STATEMENT OF SIGNIFICANCE

The cluster of 20 log cabins in the Chisana historic district stand as the best reminder of the log communities of gold rush Alaska. The "Shushana" stampede of 1899 simplified the small scale gold rushes prevalent during Alaska's gold rush era. The resultant log community of Chisana grew to a reported 400 log cabins, and at that time claimed the largest log cabin community in Alaska if not in North America (according to at least one over zealous gold rush editor). Chisana was like most gold rush camps that grew and prospered for a season or two then declined to a mere existence or abandonment. A surprising number of the remaining log cabins are associated with the characters of gold rush boom towns: prospector, dog musher, merchant, saloon man, and the keepers of law and order.

story

In May 1913, Billy James, his wife, Matilda Wales, and Nels P. "North Pole" Nelson discovered placer gold in Bonanza Creek. Nelson traveled to Dawson for grub and sparked the rush. An estimated 2,000 headed for the diggings that summer. A fleet of small steamboats left Dawson and Fairbanks and ran up the Tanana and White Rivers to near the strike; White Pass and Yukon route officials promoted a cross country route for stampedeers from the Yukon Territory via Whitehorse; but the ever dominant route was from Shushana Junction (now McCarthy) on the Copper River Northwestern Railway across the Wrangell Mountains by trail some 80 miles to the diggings via the Scolai Pass or Nizina-Chisana Glaciers, two of the most rugged routes ever crossed by a gold stampede.

The stampedeers staked the creeks for 25 miles around Gold Hill, while merchants staked three townsites. Chisana townsite (also called Chathanda City and Johnson City) became the dominant community after a miners' meeting moved the U.S. Commissioner's and recorder's office and post office to the new town in September 1913. Log cabins went up quickly during the fall and winter. The growth of Chisana was such a result of the mining decline of Nome, Fairbanks, and Dawson as the belief that the new gold fields would be permanent and extensive. Only the tributaries of Bonanza and Chisana Creeks, however, proved productive. The population quickly dropped and by 1920 the census taker found only 148 residents in the vicinity. In 1939 the post office closed.

NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY -- NOMINATION FORM

DATE ENTERED

CONTINUATION SHEET

ITEM NUMBER

8

PAGE

Of the reported 400 cabins of 1913-14, only a handful remain. Fortunately some of these are associated with prominent gold rush participants. North Pole Nelson, one of the discoverers, went on a fling "outside," squandered his gold, and came back to spend a half century looking for another strike. Two of his cabins stand in Chisana: one built ca. 1913-14, the other in the 1930s. His ashes were buried in 1965 by local miners on top of King Mountain nearby. Nelson's partner, Billy James and James's wife, Matilda Wales, also lost their money and lived in a cabin adjacent to North Pole's. The partners, however, spent most of their time in suits over mining ground or Chisana property. James, a veteran of the Klondike and a half dozen other gold rushers died in 1956, 20 years after Matilda.

On First Avenue is the cabin of Sidney "Too Much" Johnson, the dog sled freight and express musher who carried goods and 200 pounds of mail from the railroad 73 miles over frozen rivers, the Nizina and Chisana Glaciers, up the Whiskey Hill grade, and down into Chisana. Johnson received his nickname from his penchant to unload freight on the glacier when the weight got to be "too much." Nelson, James, and Johnson, symbolize Alaska, its sourdough miner and its musher; Matilda represents the little recognized woman's role in Alaska history.

Other structures dating from the rush include typical gold rush businesses: post office, blacksmith shop, saloon, and mercantile. These were part of Chisana's business district: a row of mercantiles, restaurants, barbers, harness, tin and assay shops, saloons, and other mining camp enterprises on "First Avenue." Fires and flooding have taken most of these structures, but the semblance of a street can be seen from the old post office to the present Wrangell R ranch cookhouse (historic mercantile).

Law and order was present early in Chisana and physical reminders are still present in the U.S. Commissioner's buildings. The White River district commissioner rushed to the diggings with the stampedeers, but lost his job when the office was renamed Chisana. Chisana's first commissioner was Anthony J. Dimond, a miner turned lawyer. Tony Dimond established the presence of law and order, with the help of veteran Deputy U.S. Marshall Frank H. "Al" Hoffman. A stampeder from Nome, Anthony McGett became Dimond's assistant and recorder.

During the winter of 1913-14, a two-story "federal building" (no longer standing) constructed, two jails built (one for men, the other for women) and log residences moved into. Dimond left with the "bust" in the summer of 1914. He later became prominent in politics as Alaska's sole delegate to Congress (1933-1944). Hoffman

McGettigan remained. Following two short term appointees, McGettigan became commissioner. He served the community for 25 years (1914-39) as recorder or commissioner, or postmaster (Chisana's last) and sometimes miner. Three structures associated with law and order remain--the later U.S. Commissioner's Court (which may have been Deputy Marshall Hoffman's residence), U.S. Commissioner's residence (probably McGettigan's), and women's jail. Wooden details on the Commissioner's buildings and the women's jail show outstanding log craftsmanship, from hand carved wooden door knobs and hinges to decorative diamond-shaped, wood details around window trim. McGettigan's association with the structures has yet to be determined. Unfortunately, the early Chisana records were destroyed by fire. Thus building histories can only be pieced together from period newspapers and the reminiscences of old timers.

A Native village was adjacent to the town (no structures remain). Four Native graves with their Russian Orthodox crosses and small grave houses stand on a rise overlooking the town. The vacant townsite area includes historical archeology potential.

With the construction of the airstrip ca. 1930, new buildings were built at the town's eastern end. An airstrip extension in 1956 and the introduction of fly-in hunting and guide services, brought about preservation of buildings through use. Population has saved Chisana from modern intrusions. A walk through the cluster of old structures gives one the sense of scale and ambience of a typical Alaskan gold mining camp's first season of growth.

9 MAJOR BIBLIOGRAPHICAL REFERENCES

Newspapers, 1913-1915; Chitina Leader, Cordova Daily Alaskan, Fairbanks Weekly Times, Dawson Daily News, Skagway Alaskan.

Oral interviews: Neil Finnesand, stampede participant, August 1983; Ivan Thorall, long-time resident, July 1982, June 1983; Terry Overly, long-time resident, June 1983; Ray McNutt, long-time resident, July 1982, June 1983.

10 GEOGRAPHICAL DATA

ACREAGE OF NOMINATED PROPERTY 30

UTM REFERENCES

A [N] [4] [4] [5] [2] [0] [0] 6 8 8 1 8 5 0

ZONE EASTING NORTHING

C [S] [W] [4] [4] [5] [2] [0] [0] 6 8 8 1 6 5 0

B [N] [E] [4] [4] [5] [8] [0] [0] 6 8 8 1 8 5 0

ZONE EASTING NORTHING

O [S] [E] [4] [4] [5] [8] [0] [0] 6 8 8 1 6 5 0

VERBAL BOUNDARY DESCRIPTION

The boundary commences at a point on Johnson Creek due south of the northeastern corner of airfield, thence due north to a point approximately 1,000 feet, thence 2,500 feet west to a corner point; thence 90° due south 100 feet to a corner point Johnson Creek, thence 90° back to point of origin.

LIST ALL STATES AND COUNTIES FOR PROPERTIES OVERLAPPING STATE OR COUNTY BOUNDARIES

STATE	CODE	COUNTY	CODE
-------	------	--------	------

NA

STATE	CODE	COUNTY	CODE
-------	------	--------	------

11 FORM PREPARED BY

NAME / TITLE

Robert L. Spude, Regional Historian and Michael Lappen, Historian

ORGANIZATION

Alaska Regional Office, National Park Service

DATE

May 1984

STREET & NUMBER

2525 Gambell Street, Room 107

TELEPHONE

907/271-4238

CITY OR TOWN

Anchorage,

STATE

Alaska

12 CERTIFICATION OF NOMINATION

STATE HISTORIC PRESERVATION OFFICER RECOMMENDATION


YES ☒

NO ☐

NONE ☐

Timothy A. Smith, Deputy
STATE HISTORIC PRESERVATION OFFICER SIGNATURE

In compliance with Executive Order 11593, I hereby nominate this property to the National Register, certifying that the State Historic Preservation Officer has been allowed 90 days in which to present the nomination to the State Review Board and to evaluate its significance. The evaluated level of significance is ☐ National ☐ State ☐ Local.



442000' E. IMC CARTHY D-31

U.S. GEOLOGICAL SURVEY, RESTON, VIRGINIA-1978

43

44


45

46

47



ROAD CLASSIFICATION



CHISANA SITE PLAN

SCALE 1" = 200'



LEGEND:

- | | |
|---------------------------------|----------------------------------|
| A. U S COMMISSIONER'S COURT | L. SECOND N.P. NELSON CABIN |
| B. U S COMMISSIONER'S RESIDENCE | M. RAY McNUTT - UNFINISHED CABIN |
| C. WOMEN'S JAIL | N. RAY McNUTT - STORAGE SHED |
| D. SALOON | O. RAY McNUTT - OLD CACHE |
| E. EARL HERST CABIN | P. RAY McNUTT - COOKHOUSE |
| F. OLD POST OFFICE | Q. RAY McNUTT - STORAGE SHED |
| G. CACHE | R. RAY McNUTT - GARAGE |
| H. BLACKSMITH'S SHOP | S. RAY McNUTT - MAIL CABIN |
| I. FIRST N.P. NELSON CABIN | T. RAY McNUTT - RESIDENCE |
| J. TOO MUCH JOHNSON CABIN | U. SMOKEHOUSE |
| K. LEW'S BARN AND CORRAL | V. MEAT CACHE |

pps, Stephen R., The Chisana - White River District, USGS Bulletin 630, Washington, D. C.: G.P.O., 1916.

le, Terrance M., "Historic Use of the Chisana and Nabesna Rivers, Alaska," State of Alaska, Department of Natural Resources, May 197

uening, Ernest, The State of Alaska. New York: Random House, 195

ilvie, William, Early Days on the Yukon. London: J. Lane, 1913.

cks, Melvin B., Alaska's Postmasters and Postoffices 1867-1963. Ketchikan, Alaska: Tongass Publishing Co., 1965.

llins, Alden M., compiler. Census of Alaska: Numbers of Inhabitants, 1792-1970. Anchorage: University of Alaska, 1978.

erwood, Morgan B., Big Game in Alaska, A History of Wildlife and People. New Haven: Yale University Press, 1981.

wspapers: Chitina Reader, 1910-1916.
Cordova Alaskan, 1913-1915.
Dawson Daily News, 1913-1915.
Fairbanks Weekly News, 1913-1914.
Nome Daily Nugget, 1913.

terviews:

il Finnesand, Chitina, August 1983.

izabeth Hickethier, Chisana, June 1983.

y McNutt, Chisana, July 1982, June 1983.

rry Overly, Chisana, June 1983.

an Thorall, Chisana, July 1982, June 1983.

HISTORIC AMERICAN BUILDINGS SURVEY

FIELD NOTE BOOK

Building WOMEN'S JAIL

Address

City or Vicinity CHISANA

County and State

Chief of Party:

ROBERT SPUDE

Measured By:

DAVID C. ANDERSON

STEVEN N. PETERSON

Dates Measured 18 JUNE 1983, 17 JULY 1982

HABS Survey No.

WOMEN'S JAIL (REHABILITATION)

ROOF CONDITION:

GAD - CONSIDERABLE ROT & DECAY
ROOFING SLATS DETRIMENTAL & MISSING IN PLACES
LARGE HOLE (4' x 6') ON SOUTH SIDE - CAUSED BY COLLAPSE OF A CEILING MEMBER.
RIDGE BEAMS & WALL PLATES IN GOOD CONDITION
CEILING MEMBERS GOOD ON UNDERSIDE - ROTTED ON TOP WHERE IN CONTACT WITH FOD INSULATION.
PORCH CEILING DETRIMENTAL.

TREATMENT:

REMOVE ALL ROOFING MEMBERS EXCEPT WALL PLATES & RIDGE BEAM.
BUILD NEW ROOF USING 2x4 BRUCE RAFTERS ON 16" CENTERS (FROM RIDGE START RAFTERS 8" OUT FROM OUTSIDE OF WEST WALL & PLACE ONE RAFTER ON CENTER OF WALL ON EACH SIDE).
SET A 1"x6" RIDGE BOARD ON TOP OF RIDGE BEAM & NAIL RAFTERS TO IT.
CENTER ANOTHER RAFTER OVER THE EAST WALL OF CABIN.
PUT BLOCKING BETWEEN ALL RAFTERS CENTERED OVER THE WALL PLATES ON BOTH SIDES.


PLACE 1"x6" (RANDOM WIDTHS OK - 1"x6" MINIMUM IF POSSIBLE) BOARDS ACROSS RAFTERS.


CUT ROOFING BOARDS FLUSH W/ OUTSIDE RAFTERS
TOE NAIL RAFTERS TO WALL PLATE W/ 16d NAILS
NAIL ROOFING BOARDS 2-3 NAILS PER RAFTER. (IF BOARDS ARE NOT LONG ENOUGH FOR FULL LENGTH OF BUILDING CUT SHORTER BOARDS SO THAT THEY BUT TOGETHER ON TOP OF A RAFTER. STAGGER THE JOINTS SO THAT THEY DO ALL BREAK OVER THE SAME RAFTER.)

USE 29 GAUGE TIN SHEETS TO COVER THE ROOF. START SHEETS AT BOTTOM BACK OF ROOF AND WORK TOWARD FRONT. WHEN DOING LATER USE FROM BACK TO FRONT. OVERLAP NOT LESS THAN 3-4" ALONG SIDES & SHEETS AND 6-8" AT TOP OF EACH LAYER.
WHEN BOTH SIDES ARE COVERED PUT A RIDGE PIECE ALONG THE TOP. (DO NOT LAPPING EACH SIDE AT LEAST 8")
USE GALVANIZED ROOFING NAILS SPACED EVERY 6" FOR ROOFING TIN.
ON ENDS AND ALONG THE FASCIA. BEND THE TIN DOWN TO COVER THE BOTTOM OF THE ROOFING MEMBERS.


ADDITIONS:


PLACE 1"x4" FASCIA BOARDS ALONG CUT ENDS OF RAFTERS. (NAIL w/ 3-16d NAILS @ EACH RAFTER.)
80 LB ROOFING FELT UNDER TIN ROOFING.





ROOF PLAN
 SCALE: $\frac{1}{4}" = 1'-0"$






FLOOR & FOUNDATION

CONDITION:

FLOOR IN MAIN CABIN IN GOOD SHAPE - NO HOLES OR HOLLOW SPOTS - REASONABLY LEVEL & FLAT.
 PORCH FLOOR INADEQUATE. BOARDS SOFT AND LOOSE. SUPPORT STRINGER AT FRONT PORCH ROTTING UNDER STORAGE AREA.
 FOUNDATION QUESTIONABLE. DIGGING UNDER SOUTH EAST CORNER YIELDED SOFT MUD, MOSS, ROT & A FEW STONES THE LARGEST OF WHICH WAS 4" DIAMETER.


TREATMENT:

CORNERS OF THE MAIN CABIN SHOULD BE DUG OUT TO 10-12". LARGE STONES FROM RIVER BED SHOULD THEN BE WEDGED FIRMLY IN PLACE UNDER THE STRUCTURE. SAME SHOULD BE DONE AT THE FRONT TWO CORNERS OF THE PORCH.
 THE EXISTING STRINGER UNDER THE FRONT OF THE PORCH SHOULD BE REMOVED & REPLACED WITH A NEW 4 1/2" - 5" STRINGER - SET LEVEL WITH THE ONE AT THE FRONT OF THE PORCH.
 REMOVE THE FLOOR BOARDS FROM THE PORCH.
 ONCE THE NEW STRINGER IS IN PLACE, NEW FLOOR BOARDS (1 1/2" X RANDOM WIDTH) SHOULD BE SET IN PLACE USING 12D GALVANIZED NAILS.



9" LOOP AVE. (e 8" to 13")

VERIFY IF SOD ON TOP
OF GRABS OR BETWEEN?
ON BZ



I. CONDITION:

GOOD - SOUND LOGS ADEQUATE ENDS
PORCH ADDITION LOOSE BOARDS IN ADEQUATE BACKING
ROOF SUPPORT @ SOUTHWEST CORNER ADEQUATE
WINDOW CASING & TRIM GOOD (SEE "WINDOWS & DOOR")

TREATMENT:

RE-CHINK ANY GAPS BETWEEN LOGS w/ MOSS
NAIL 2"x4" STUD AGAINST LOG WALL BEHIND PORCH STORAGE ROOM WALL - REIN
BOARDS TO THE NEW STUD w/ 12d GALVANIZED NAILS
REPLACE 1/2" x 1/2" PATTERNS ON BACK SIDE OF BOARDS (7 TOTAL ON SOUTH
WALL OF STORAGE ROOM)

II. CONDITION:

STRUCTURALLY SOUND w/ GAPS BETWEEN SOME LOGS.
TWO HOLES NEAR TOP (ONE DIRECTLY BELOW RIDGE BEAM 6"-9"; ONE UNDER
EAVE ON SOUTH SIDE OF GABLE)
Window Casings & TRIM IN GOOD SHAPE (SEE "WINDOWS & DOOR")

TREATMENT:

RECHINK ANY GAPS BETWEEN LOGS w/ MOSS
FILL TWO HOLES NEAR TOP w/ PIECES OF LOGS CUT & NAILED w/ 12d
GALVANIZED NAILS & CHINKED w/ MOSS.
REMOVE ANTENNA POLE

III. CONDITION:

GOOD - SOUND LOGS w/ GAPS BETWEEN SOME LOGS.
SUPPORT FOR WALL PLATE @ FRONT OF PORCH LOOSE
WINDOW TRIM & CASING GOOD. GLAZING INTACT

TREATMENT:

RECHINK ANY GAPS BETWEEN LOGS w/ MOSS.
REPLACE PORCH POST w/ NEW 5" PEELED WHITE SPRUCE LOG. (CUT, NOTCH IN
TO ACCEPT WALL PLATE - THE JOE NAIL IN w/ 12d GALVANIZED NAILS)

IV. PORCH CONDITION

CABIN WALL GOOD w/ SMALL GAPS BETWEEN LOGS.
Porch FRAME & TRIM GOOD
PORCH ADDITION WALL OK. ROOF OVER PORCH ADDITION LOOSE: CANVING ON
PORCH ADDITION ROOF SHOWING AGE.
DOOR TO STORAGE WON'T SHUT BECAUSE OF SETTLING OF PORCH.

TREATMENT:

RECHINK ANY GAPS w/ MOSS
REMOVE CANVING FROM TOP OF STORAGE ROOM & REPLACE w/ ROOFING FELT.
REMOVE POST @ NORTH EAST CORNER OF STORAGE & REPLACE w/ LONGER 2"x4" ST
ATTACHED TO RAFTER (CENTER POST 1/2" UP.)

HISTORIC AMERICAN BUILDINGS SURVEY

FIELD NOTE BOOK

Building U.S. COMMISSIONER'S COURT

Address.....

City or Vicinity CHISANA, ALASKA

County and State

Chief of Party:

ROBERT SPUDE

Measured By:

DAVID C. ANDERSON

STEVEN N. PETERSON

Dates Measured 15, JULY 1982, 21 JUNE 1983

HABS Survey No.

ROOF

CONDITION:

ROOF - SOD ROOF ROTTING TOPS OF CEILING MEMBERS. (9' x 4' to 6" HALF SPLIT
WHICH SPANNE LOGS AND SHIT SIDE. DOWN 4' 6" ON WEST SIDE.)
NEWER ROOF ON TOP W. FELT PAPER - FAIRLY GOOD SHAPE - NO SHEATHS GROWING
LIGHTLY ASYMMETRICAL W/ RIDGE SHIFTED TO EAST. (In front - Symmetrical
STRUCTURAL MEMBERS - RIDGE FURLING & PLATE LOGS IN GOOD SHAPE
"PLATE" LOGS AT GABLE ENDS MISSING SUPPORT NOTCHES FOR FASCIA B
SIDE) SEE DETAIL BELOW LEFT PAGE 12)
ROOF IN ADDITION - CHANGE IN SLOPE (TO 3:12 MAX FROM 6:12)
PLYWOOD ONLY 2" RAFTER LOGS 16" OC.
PLYWOOD DELAMINATING, SAGGING & WATER STAINED
RAFTERS EXPOSED TO MOISTURE - SIGNS OF DECAY - REST ON NEW LOGS
& TOP OF PITCH. SEE DETAIL #2 BELOW LEFT

TREATMENT:

REMOVE ALL ROOFING MEMBERS OF NEWER ROOF AND ADDITION ROOF
REMOVE SOD & CEILING MEMBERS OF MAIN CABIN
← SET NEW PLATE LOG SUPPORTS ON GABLE ENDS W/ NOTCHES FOR FASCIA
REPLACE CEILING MEMBERS W/ 4-6" SPLIT LOGS (W. SPOUXE) SET 3/4" IN
DOWN - 4" ON EAST SIDE - 4' 6" ON WEST
SET NEW 9" RAFTERS ON ADDITION - 16" OC
NAIL 1" x RANDOM WITH HEADS ACROSS ADDITION RAFTERS (AS PER DETAIL
#2) 18" METAL FLASHING AT JUNCTIONS
TAP PAPER OVER BOTH ROOFS
METAL SHEET ROOFING (SMALL SHEETS "DESIGNED TO PULL OR PARTIALLY RUST")
→ PLACE 4-5" FASCIA LOG ALONG ENDS OF CEILING MEMBERS - SETTING IN
"PLATE" LOGS - DOWEL/PIN INTO POSITION.


WALLS

SOOTHL CONDITION:

SETTLED & LEAKING - MAJOR SAYS TO RIGHT OF PORCH DOOR.
SILL LOGS WEAKENING - PROBABLE CAUSE OF SETTLING
PLANK/BOARD COVERING GAP TO LEFT OF PORCH DOOR HEADER (THIN)
MAIN CABIN LOGS CUT IN FLAT TO TAKE FLAT TRIM (1 3/4" THICK) ON PORCH SIDE
NEWER FLAT INSIDE W/ 3/8" TRIM.
BOTH SOUTH WALLS LEAKING FROM PLATE LOGS UP.


TREATMENT:

REMOVE BOARDS FROM OUTER LEFT SIDE (INSIDE & OUTSIDE)
REMOVE TRIM BOARD OF HUDSON BAY SECTION ON RIGHT SIDE - RE-ATTACH PIND
HUDSON BAY CONNECTION AT ALL POINTS.
SET ONE NEW NOTCHED LOG INTO EACH SIDE OF FRONT & TOP WHEN PLATE
HAS BEEN REPLACED. (SILL LOGS 3")
NOTE: SAME PROBLEM & SOLUTION ON WEST SIDE OF PORCH ALSO.




#1 DETAIL - GABLE END FASCIA

SCALE . NONE



#2 DETAIL NOT TO SCALE



#3 DETAIL N.T.S.

#4 PLAN DETAIL N.T.S.

DECAYING - THE REST INCLUDING PLATE LOG IN ADDITION
 PROBLEM @ CONNECTION OF ADDITION: CABIN LOGS GROOVED
 ACCEPT LOG WALL OF ADDITION (SEE DETAIL #1)
 PROBLEM WHERE WALL & ROOF MEET ROOF OF CABIN (DETAIL #2)
 MANY OF THE 4 1/2" - 5" LOGS ON THE ADDITION HAVE BIRD KEPS
 90% of the way THROUGH THE LOGS IN MIDDLE OF THE
 WALL - FINISH OUT ASHT
 WINDOWS FROM ADDITION MAY HAVE COME FROM MAIN CABIN WHEN
 POOL IS NOW - CASING SLIGHTLY SPALLED AT BOTTOM -
 BUILT FOR THE FRAME.
 ADDITION LOGS: PILED IN INSIDE & OUT
 MAIN CABIN LOGS UNPEELED & HEAVY FLAT INSIDE
 MILDEW FORMING ON TOP LOGS OF SOUTH WALL OF ADDITION

TREATMENT

REMOVE & REPLACE BOTTOM TWO LOGS. (12" taper to 8" x 28")
 POSSIBLY REMOVE ADDITION - WE'LL SEE
 OTHERWISE, REPLACE ALL SILL & SPANREL LOGS ON ADDITION
 REPLACE TOP 3 LOGS ON SOUTH WALL OF ADDITION
 REPAIRING NECESSARY EVERYWHERE

IF ADDITION IS REMOVED ALL LOGS ON THE WEST WALL OF THE
 MAIN CABIN SHOULD
 BE REPLACED W/ A WINDOW (THE ONE FROM THE ADDITION
 BACK UPRIGHT) SET IN WHERE THE DOOR IS PRESENTLY.

NORTH: CONDITION

GOOD: ENDS OF LOGS ON EAST SIDE SHOWING SIGNS OF DEGRADATION
 FROM WEATHERING
 8" PLATE LOG & NEXT LOG UP NEED TO BE REPLACED: THIS UNUSABLE
 LOG WITH NOTHING ON TOP VENT - BETTER DETAIL?
 BILL (SPANREL?) LOG ROTTEN, SORT

TREATMENT

REPLACE PLATE LOG & ONE ABOVE IT: 7 1/2 - 9" TAPER 18'-19' & 17')
 REPLACE SILL LOG & ONE ABOVE IT: 12-14" TAPER 17')
 CHECK ENDS w/ D. P. NOW

FLOORING: CONDITION

POOR TO BAD: SPRING IN MAIN CABIN, ROTTEN IN ADDITION & N. SIDE
 IN PORCH.

Ceiling Logs of Gable ends w/ 1/2" (and) - not split.

TREATMENT

REMOVE ALL FLOOR BOARDS & STRINGERS
 DIG DOWN TO GET AIR CIRCULATION
 FRAME IN NEW FLOOR 2" BELOW THRESHOLDS w/ 2x6's or worse
 REPLANK RUNNING N-S w/ 1-1/4 RANDOM WIDTH BOARDS.



CONSIDER FOUNDATION WALL SYSTEMS EVERYWHERE

8 1/2 -

ADDITION


MAIN CABIN

STONE

TO BED

HOPSON BY CORNERS

1/2" BY 1/2" LOKS
12 @ 4000



10' 11 1/2"

LOGS PEEL
IN & OUTSIDE. 5" LOGS.

NOTE
WHEN THIS ADDITION
WAS PUT ON A
WINDOW (PROBABLY
LIKE A) WAS TAKEN
OUT AND THE ROOM
INSTALLED.

ADDITION C2 1960

WINDOW SAME AS A


MISSIONARYS OFFICE

SANA, ALAKA

16, 1982,

EN M. PETERSON

ANCH, AK



CHOPPED EN
SHOWN
BOLD
FRAM & CARING
9 1/2 IN. H.C.
14 LBS. 6000
WINDOW FRAME
NOT FRIGOR

FRONT ADDITION
ENCLOSED APP
CABIN (MAIN)
3" LOG BORER
POLE PECK

PECKS - 2" WOOD
H.A. CORNER & ENA.


5 1/2" ROUND
LOGS IN W. BARK

6 1/2" x 1 1/2"
W. STRIKE
P. SAWN

el

19

11/11



CORNER OFF =


- NEEDS EMERGENCY ROOF
- WAS MAINTAINED TO 100%
- FLOOR GOOD NO LIFTING FLOOR, WALL, CEILING
- FLOOR LEVEL = GOOD PROBABLY MISSING TRAIL

WAS TO CORNER POST

NOSE LINKING

NOTE ELEV OF FRONT CORNERS OFFICE

NOTE TOP TRIM LOWERED
POSS WHEN NEW SASH
INSTALLED




INSIDE ELEV.

CORNER OFFICE WINDOW (A)

1" x 3 3/8"

1" x 1 3/8" STOP ON POT. ONLY



OUTSIDE ELEV.

CORNER OFFICE WINDOW (A)

ROOF - ± 1962

4 BRED C. SPKES

ROOM W.
NK ROOF

3 1/2 x 3 1/2

2 1/2 x 4" PAPER
3' 5" OC

TOP ROOF

SPUT FACE IN

4' 6"

10' 5"

SEE PLAN.

6x6

7' 2"

DOUBLE "X" NOTCHED JT

Log? STEINKEPERS

SIL LOGS

SECTION COMM. ATTUE: "B.B."

MOON CHINK

11' 3"

9"


ROUNDED TO
ROOF GIVE

SPUT FACE B
QUE. POLE END

HEADER LOG (NOTCHED ONLY)

ROOF BECK: 3 1/2" TO
LOG ITALVES - H
SPUT.

PURLINS: 3" TIP T
12" BUTT S - PEELE



HISTORIC AMERICAN BUILDINGS SURVEY

FIELD NOTE BOOK

Building U.S. COMMISSIONER'S RESIDENCE

Address

City or Vicinity CITISANA

County and State

Chief of Party:

ROBERT SPURD

Measured By:

DAVID C. ANDERSON

STEVEN N. PETERSON

Dates Measured 15 JULY, 1982., 19 JUNE 1983

HABS Survey No.

COMPASSIONATE RESIDENCE (CHISANA, WEST)

(REHABILITATION)

ROOF:

CONDITION:

EAST - WILLOWS & VARIOUS OTHER PLANTS GROWING IN VARIOUS PLACES.
THE PAPER COVERING MISSING. SOMETHING BADLY WEATHERED.
ROOF SYSTEM CONSISTS OF TWO PARTS:

- ORIGINAL ROOF SPLIT LOGS (AID SPLIT DOWN ON RIDGE BEAM, PURLINS & PLATE LOGS W/ SOD INSULATION ON TOP. EAST ENDS AT LOGS ARE ROTTING & FALLING OFF; UNDER-SIDE COVERED W/ CURLAP - HARD TO SEE, BUT SIGNS OF DECAY & DAMAGE ON WEST SIDE SOILING.
- NEWER ROOF CONSISTS OF A RAFTER SYSTEM LAID ON TOP OF SOD & FLESH ROOF. A PURLIN RUNS ALONG THE PLATE LOG RAFTERS & PURLINS SHOWING SIGNS OF DETEIORATION & DECAY. BOARDS WERE PLACED ACROSS THE RAFTERS W/ TAR PAPER OR ASPHALT OVER THEM. FASCIA BOARDS ARE WAXED, WEATHERED OR MISSING.

ROOF SEEMS EXACTLY ALONG BOTH SIDES. DUE MOSTLY TO ROTTING PURLINS & MISSING PORTION OF THE SOILING, THAT SUPPORTS THE SECOND ROOF. BUT ALSO DUE TO THE APPARENT DECAY OF THE PLATE LOGS & THE WAY THE WALL LEANS. RIDGE BEAMS, PURLINS APPEAR TO BE IN GOOD SHAPE.

TREATMENT:

- REMOVE NEWER ROOF (SHEATHING, RAFTERS & PURLINS) AND REMOVE SOD/MAN INSULATION. (THIS MAY REVEAL THAT TOO MUCH DECAY HAS OCCURRED IN THE SPLIT LOG RAFTERS TO KEEP THEM, IN WHICH CASE THE CEILING W/ ITS TAN CURLAP COVERING MAY BE LOST. IT WOULD THEN BE NECESSARY TO REMOVE THE CURLAP & THE CEILING LOGS COMPLETELY.)
- CUT & FIT 2"x4" RAFTERS @ 16" CENTERS W/ A 1"x8" RIDGE BOARD OVER THE RIDGE BEAM. THE RAFTERS SHOULD EXTEND 16" BEYOND OUTSIDE OF PLATE LOG. ATTACH 1"x4" FASCIA PARALLEL TO EXTENDED ENDS OF RAFTERS AND PUT 2"x4" BLOCKING BETWEEN THE RAFTERS ALONG THE TOP OF THE PLATE LOG. (IN ORDER TO REPLACE THE CURLAP IT WOULD BE NECESSARY TO PUT A PLYWOOD CEILING IN UNDER THE RAFTERS. IT COULD EITHER BE SET FIRST BY PUTTING THE PLYWOOD ON TOP OF THE RIDGE BEAM, PURLINS & PLATE LOG AND SETTING THE RAFTERS ON TOP OF THE PLYWOOD OR BY CUTTING THE PLYWOOD TO FIT UP BETWEEN THE PURLINS AND NAILING IT TO THE RAFTERS.)
- 1" X RANDOM WIDTH BOARDS SHOULD THEN BE NAILED ACROSS THE RAFTERS W/ 2" PLY ROOFING FELT ROBBED OVER THAT.
- A TIN (EITHER ALUMINUM SHEETS OR CORRUGATED TIN ROOFING) ROOF NEEDS TO BE PLACED ON TOP OF THAT.

(REFER TO "WOMEN'S JAIL" FOR FURTHER DETAILS.)

- ADDITION: REMOVE PLATE LOGS ON EAST & WEST WALLS, AND RE-PLUMB BOTH WALLS WHERE THEY LEAN IN AT THE MID-POINT. (NOTE: CROSS BRACING MAY BE REQUIRED UNTIL NEW PLATE LOGS ARE SET IN PLACE.)
- PUT NEW PLATE LOGS IN ATTACHING THEM W/ 12" SPIKES (EVERY 2-3 FEET) TO THE REST OF THE WALL.
- ALSO: ROOF SHOULD EXTEND TO THE ENDS OF THE RIDGE, PURLINS & PLATE LOGS AT THE FRONT & BACK OF THE BUILDING, AND A RAFTER SHOULD BE CENTERED OVER EACH WALL.

WALLS:

EARLY NEED TO BE SET IN SUCH A WAY AS TO RAISE THE CORNER OF THE LOG. CHINKING SHOULD BE DONE OUT FIRST TO MAKE IT EASIER TO CLOSE THE GAP.
WHEN THE CORNER HAS BEEN RAISED SUFFICIENTLY TAKE PLAT LOGS & BE PLACED UNDER THE CORNER AS A FOUNDATION (CORNER SHOULD BE LIFTED $\frac{3}{4}$ - 1" HIGHER THAN ULTIMATELY NECESSARY TO ALLOW SETTLING & PLACEMENT OF THE ROCKS)
BACK FILL W/ DIRT
RECHINK THE WALL W/ MOSS TO FILL ANY GAPS.
TAP WOODEN DOWELS BACK INTO THE TRIM PIECES UNTIL THEY ARE DO NOT SPLIT THE TRIM!

WEST: CONDITION:

FAIR TO GOOD. MOST LOGS SOUND W/ THE PROBABLE EXCEPTION OF THE LOG WHICH SEEMS TO HAVE DETERIORATED BY EXPOSURE TO THE SUN & THE ORIGINAL ROOF.
WINDOW HEAVILY WEATHERED BUT OTHERWISE OKAY. ONE PIECE OF CHINK TRIM MISSING FROM OUTSIDE. ONE PANE OF GLASS MISSING - THE OTHER BECOMEN.
LARGE (UP TO 1") GAPS BETWEEN MAIN CABIN LOGS & LOGS FOR FRONT PORCH.
LARGE GAP UNDER WINDOW SILL.
WALL LEANS IN 3-4" INCHES IN THE MIDDLE AT THE TOP "DOWN" TO THE PLATE LOG.

TREATMENT:

AFTER REMOVAL OF THE ROOF & THE PLATE LOG, THE TOP OF THE LOG SHOULD BE BRACED BACK DOWN TO THE OPPOSITE WALL AND HUMBLED ONCE THE WALL.
ONCE THE WALL IS BACK TO VERTICAL THE NEW PLATE LOG (ENTER 2' BEYOND FRONT & BACK) SHOULD BE SET IN PLACE (W/ TRIM CUT TO FIT ALL 3 INTERSECTING WALLS).
AFTER SPIKING THE PLATE LOG IN PLACE THE BRACING SHOULD REMAIN IN PLACE UNTIL THE ROOF IS UP & SECURED.
CHINK ALL GAPS BETWEEN LOGS (BOTH VERTICAL & HORIZONTAL GAPS) USE 4" SPLIT LOG OR 1x4" BOARD TO COVER GAP UNDER WINDOW.
REPLACE GLASS W/ 2 - 20" X 16" SINGLE PANE'S (USE GLAZING COMPOUND & C)
REPLACE WINDOW TRIM ON RIGHT SIDE W/ SPLIT LOG PIECE
PAINT WINDOW FRAME.

NORTH: CONDITION:

GOOD.

TREATMENT:

RECHINK ANY GAPS.

EAST: CONDITION:

IDENTICAL TO WEST EXCEPT FOR THE WINDOW (DIFFERENT SIZE)


TREATMENT:

SAME AS WEST: EXCEPT USE 2 - 14" X 20" PANE'S OF GLASS

SCALE 3/8" = 1' 0"




Magnetic North



Plan North
66° EAST



TRUCK M
2000
Mason



SCALE $\frac{3}{8}" = 1'-0"$

THREE PANE SAWING TYPE
WINDOW (ALL 3 PANES INTACT)

INSIDE FLOOR 8'-24" LOWER
THAN SURROUNDING LAND
(BERMING? SETTING? 500 FROM
POOF?)

INTERIOR LOGS HOOK FLAT
W/ WALLS COVERED W/
GREEN BURLAP.

SPLIT LOG PANEL SHELVING
SYSTEM W/ CABINET UNDER
NEATH

"SPLIT LOG"
PANEL SHELVING
WINDOW # 1 on each
side (16" wide)

CEILING COVERED W/
TAN BURLAP (WEAVED
AROUND PURLINS)

PANEL DOOR W/
SLATING & SPLIT LOG
TRIM (OFF HINGES)

FRONT WALL HOOK TO
7" THICKNESS

DOOR HGT:
5'6"

SPLIT LOG TRIM
11 1/2" x 1 1/2"

SPLIT LOG PANEL SHELVING
SYSTEM

SPLIT LOG 6" W/ HOOK W/ SLATING
TRIM

BEET SECTION W/ HOOK
SPLIT LOG

SUBSTANTIAL SETTING @ FRONT
TWO CORNERS 3'-4"

DOOR HGT:
5'7"


3" THICK

PORCH: WALLS FLAT 1102422
2 LOGS HIGH; THEN
HUDSON LAY CORNER
TO RGS






WALL LENS
FROM WING
SILL TO TOP

THREE PANE
WINDOW (2
BERMING)

LOGS 1 1/2" x 1 1/2"
THICK 10' x 10'



CLABS SPILT & CUT TO WIDTH
PEELER IN MAIN CABIN



15 DIPP.
100

